

Record Information

1. Site Name: Thomason Lumber Company
(as entered in CERCLIS)
2. Site CERCLIS Number: OKD007335524
3. Site Reviewer: Ariadne Lytwyn, Fluor Daniel, Inc.
4. Date: May 24, 1994
5. Site Location: Broken Bow/McCurtain/Oklahoma
(City/County,State)
6. Congressional District:
7. Site Coordinates: Single
Latitude: 34°01'24.0" Longitude: 094°43'42.0"

Site Description

1. Setting: Unknown
2. Current Owner: Private - Industrial
3. Current Site Status: Active
4. Years of Operation: Unknown
5. How Initially Identified: Incidental
6. Entity Responsible for Waste Generation:
 - Other - wood preserving plant
 - Recyclers
7. Site Activities/Waste Deposition:
 - Surface Impoundment
 - Tanks - Above Ground

9793373



Waste Description

8. Wastes Deposited or Detected Onsite:

- Oily Waste
- Creosote
- PCP

Response Actions

9. Response/Removal Actions:

- Other Removal Action Has Occurred

RCRA Information

10. For All Active Facilities, RCRA Site Status:

- Not Applicable

Demographic Information

11. Workers Present Onsite: Unknown

12. Distance to Nearest Non-Worker Individual: Unknown

13. Residential Population Within 1 Mile: 3215.0

14. Residential Population Within 4 Miles: 5597.0

Water Use Information

15. Local Drinking Water Supply Source:

- No Water Withdrawals Within Target Distance Limits

16. Total Population Served by Local Drinking Water Supply Source: Unknown

17. Drinking Water Supply System Type for Local Drinking
Water Supply Sources:

- Unknown

18. Surface Water Adjacent to/Draining Site:

- Stream

PREscore 2.0 - PRESCORE.TCL File 05/11/93
HRS DOCUMENTATION RECORD
Thomason Lumber Company - 07/22/94

PAGE: 1

1. Site Name: Thomason Lumber Company
(as entered in CERCLIS)
2. Site CERCLIS Number: OKD007335524
3. Site Reviewer: Ariadne Lytwyn, Fluor Daniel, Inc.
4. Date: May 24, 1994
5. Site Location: Broken Bow/McCurtain/Oklahoma
(City/County,State)
6. Congressional District:
7. Site Coordinates: Single

Latitude: 34°01'24.0"

Longitude: 094°43'42.0"

	Score
Ground Water Migration Pathway Score (Sgw)	0.00
Surface Water Migration Pathway Score (Ssw)	1.36
Soil Exposure Pathway Score (Ss)	0.34
Air Migration Pathway Score (Sa)	0.57

Site Score	0.75
------------	------

NOTE

EPA uses the terms "facility," "site," and "release" interchangeably. The term "facility" is broadly defined in CERCLA to include any area where hazardous substances have "come to be located" (CERCLA Section 109(9)), and the listing process is not intended to define or reflect boundaries of such facilities or releases. Site names, and references to specific parcels or properties, are provided for general identification purposes only. Knowledge regarding the extent of sites will be refined as more information is developed during the RI/FS and even during implementation of the remedy.

GROUND WATER MIGRATION PATHWAY Factor Categories & Factors	Maximum Value	Value Assigned
Likelihood of Release to an Aquifer Aquifer:		
1. Observed Release	550	0
2. Potential to Release		
2a. Containment	10	10
2b. Net Precipitation	10	3
2c. Depth to Aquifer	5	5
2d. Travel Time	35	35
2e. Potential to Release [lines 2a(2b+2c+2d)]	500	430
3. Likelihood of Release	550	430
Waste Characteristics		
4. Toxicity/Mobility	*	1.00E+00
5. Hazardous Waste Quantity	*	100
6. Waste Characteristics	100	3
Targets		
7. Nearest Well	50	0.00E+00
8. Population		
8a. Level I Concentrations	**	0.00E+00
8b. Level II Concentrations	**	0.00E+00
8c. Potential Contamination	**	0.00E+00
8d. Population (lines 8a+8b+8c)	**	0.00E+00
9. Resources	5	0.00E+00
10. Wellhead Protection Area	20	0.00E+00
11. Targets (lines 7+8d+9+10)	**	0.00E+00
12. Targets (including overlaying aquifers)	**	0.00E+00
13. Aquifer Score	100	0.00
GROUND WATER MIGRATION PATHWAY SCORE (Sgw)	100	0.00

* Maximum value applies to waste characteristics category.
** Maximum value not applicable.

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT Factor Categories & Factors DRINKING WATER THREAT	Maximum Value	Value Assigned
Likelihood of Release		
1. Observed Release	550	0
2. Potential to Release by Overland Flow		
2a. Containment	10	10
2b. Runoff	25	2
2c. Distance to Surface Water	25	25
2d. Potential to Release by Overland Flow [lines 2a(2b+2c)]	500	270
3. Potential to Release by Flood		
3a. Containment (Flood)	10	10
3b. Flood Frequency	50	25
3c. Potential to Release by Flood (lines 3a x 3b)	500	250
4. Potential to Release (lines 2d+3c)	500	500
5. Likelihood of Release	550	500
Waste Characteristics		
6. Toxicity/Persistence	*	1.00E+02
7. Hazardous Waste Quantity	*	100
8. Waste Characteristics	100	10
Targets		
9. Nearest Intake	50	0.00E+00
10. Population		
10a. Level I Concentrations	**	0.00E+00
10b. Level II Concentrations	**	0.00E+00
10c. Potential Contamination	**	0.00E+00
10d. Population (lines 10a+10b+10c)	**	0.00E+00
11. Resources	5	0.00E+00
12. Targets (lines 9+10d+11)	**	0.00E+00
13. DRINKING WATER THREAT SCORE	100	0.00

* Maximum value applies to waste characteristics category.
 ** Maximum value not applicable.

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT Factor Categories & Factors HUMAN FOOD CHAIN THREAT	Maximum Value	Value Assigned
Likelihood of Release		
14. Likelihood of Release (same as line 5)	550	500
Waste Characteristics		
15. Toxicity/Persistence/Bioaccumulation	*	5.00E+04
16. Hazardous Waste Quantity	*	100
17. Waste Characteristics	1000	32
Targets		
18. Food Chain Individual	50	0.00E+00
19. Population		
19a. Level I Concentrations	**	0.00E+00
19b. Level II Concentrations	**	0.00E+00
19c. Pot. Human Food Chain Contamination	**	3.00E-06
19d. Population (lines 19a+19b+19c)	**	3.00E-06
20. Targets (lines 18+19d)	**	3.00E-06
21. HUMAN FOOD CHAIN THREAT SCORE	100	0.00

* Maximum value applies to waste characteristics category.
 ** Maximum value not applicable.

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT Factor Categories & Factors ENVIRONMENTAL THREAT	Maximum Value	Value Assigned
Likelihood of Release		
22. Likelihood of Release (same as line 5)	550	500
Waste Characteristics		
23. Ecosystem Toxicity/Persistence/Bioacc.	*	5.00E+05
24. Hazardous Waste Quantity	*	100
25. Waste Characteristics	1000	56
Targets		
26. Sensitive Environments		
26a. Level I Concentrations	**	0.00E+00
26b. Level II Concentrations	**	0.00E+00
26c. Potential Contamination	**	4.00E+00
26d. Sensitive Environments (lines 26a+26b+26c)	**	4.00E+00
27. Targets (line 26d)	**	4.00E+00
28. ENVIRONMENTAL THREAT SCORE	60	1.36
29. WATERSHED SCORE	100	1.36
30. SW: OVERLAND/FLOOD COMPONENT SCORE (Sof)	100	1.36

* Maximum value applies to waste characteristics category.
 ** Maximum value not applicable.

SOIL EXPOSURE PATHWAY Factor Categories & Factors RESIDENT POPULATION THREAT	Maximum Value	Value Assigned
Likelihood of Exposure		
1. Likelihood of Exposure	550	550
Waste Characteristics		
2. Toxicity	*	1.00E+02
3. Hazardous Waste Quantity	*	100
4. Waste Characteristics	100	10
Targets		
5. Resident Individual	50	0.00E+00
6. Resident Population		
6a. Level I Concentrations	**	0.00E+00
6b. Level II Concentrations	**	0.00E+00
6c. Resident Population (lines 6a+6b)	**	0.00E+00
7. Workers	15	5.00E+00
8. Resources	5	0.00E+00
9. Terrestrial Sensitive Environments	***	0.00E+00
10. Targets (lines 5+6c+7+8+9)	**	5.00E+00
11. RESIDENT POPULATION THREAT SCORE	**	2.75E+04

* Maximum value applies to waste characteristics category.

** Maximum value not applicable.

*** No specific maximum value applies, see HRS for details.

SOIL EXPOSURE PATHWAY Factor Categories & Factors NEARBY POPULATION THREAT	Maximum Value	Value Assigned
Likelihood of Exposure		
12. Attractiveness/Accessibility	100	1.00E+01
13. Area of Contamination	100	5.00E+00
14. Likelihood of Exposure	500	5.00E+00
Waste Characteristics		
15. Toxicity	*	1.00E+02
16. Hazardous Waste Quantity	*	100
17. Waste Characteristics	100	10
Targets		
18. Nearby Individual	1	1.00E+00
19. Population Within 1 Mile	**	3.00E+00
20. Targets (lines 18+19)	**	4.00E+00
21. NEARBY POPULATION THREAT SCORE	**	2.00E+02
SOIL EXPOSURE PATHWAY SCORE (Ss)	100	0.34

* Maximum value applies to waste characteristics category.
 ** Maximum value not applicable.

AIR PATHWAY SCORESHEET

Thomason Lumber Company - 07/22/94

AIR MIGRATION PATHWAY Factor Categories & Factors	Maximum Value	Value Assigned
Likelihood of Release		
1. Observed Release	550	0
2. Potential to Release		
2a. Gas Potential to Release	500	390
2b. Particulate Potential to Release	500	110
2c. Potential to Release	500	390
3. Likelihood of Release	550	390
Waste Characteristics		
4. Toxicity/Mobility	*	2.00E+00
5. Hazardous Waste Quantity	*	100
6. Waste Characteristics	100	3
Targets		
7. Nearest Individual	50	2.00E+01
8. Population		
8a. Level I Concentrations	**	0.00E+00
8b. Level II Concentrations	**	0.00E+00
8c. Potential Contamination	**	2.00E+01
8d. Population (lines 8a+8b+8c)	**	2.00E+01
9. Resources	5	0.00E+00
10. Sensitive Environments		
10a. Actual Contamination	***	0.00E+00
10b. Potential Contamination	***	2.20E-02
10c. Sens. Environments (lines 10a+10b)	***	2.20E-02
11. Targets (lines 7+8d+9+10c)	**	4.00E+01
AIR MIGRATION PATHWAY SCORE (Sa)	100	5.68E-01

* Maximum value applies to waste characteristics category.

** Maximum value not applicable.

*** No specific maximum value applies, see HRS for details.

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Pond A (Separation)

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID		Pond A (Separation)	
b. Source Type		Surface Impoundment	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd3/gal)	Source Area (ft2)	2300.00	6400.00
e. Source Volume/Area Value		9.20E+02	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		9.20E+02	

Documentation for Source Type:

Pond A is an unlined surface impoundment with demensions of approximatly 80 feet by 80 feet by 10 feet (Ref.2 p.11).

Reference: 2

Documentation for Source Volume:

The dimensions of Pond A are 80 ft x 80 ft x 10 ft (Ref.2 p.11).

Convert to yards: $80 \text{ ft} \times \frac{0.33 \text{ yds}}{1 \text{ ft}} = 26.4 \text{ yds}$

$10 \text{ ft} \times 0.33 \text{ yds} = 3.3 \text{ yds}$

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

1 ft

Multiply the dimensions: 26.4 yds x 26.4 yds x 3.3 yds = 2299.97
cubic yards

Reference: 2

Documentation for Source Area:

The area of Pond A is 80 ft by 80 ft (Ref. 2 p.11).

Reference: 2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Pond B

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID		Pond B	
b. Source Type		Surface Impoundment	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd3/gal)	Source Area (ft2)	336.90	625.00
e. Source Volume/Area Value		1.35E+02	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		1.35E+02	

Documentation for Source Type:

Pond B is a surface impoundment filled with sawdust to act as filter aid (Ref.2, p. 12).

Reference: 2

Documentation for Source Volume:

The dimensions of Pond B are 25 ft x 25 ft and 15 ft deep (Ref. 2, p.12).

Convert to yards: $25 \text{ ft} \times 0.33 \text{ yds} = 8.25 \text{ yds}$
1 ft

$$\begin{array}{l} 15 \text{ ft} \times 0.33 \text{ yds} = 4.95 \text{ yds} \\ 1 \text{ ft} \end{array}$$

$$8.25 \text{ yds} \times 8.25 \text{ yds} \times 4.95 \text{ yds} = 336.90 \text{ cubic yards}$$

Reference: 2

Documentation for Source Area:

The area of Pond B is 25 ft by 25 ft (Ref.2, p. 12).

Reference: 2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Pond C

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID		Pond C	
b. Source Type		Surface Impoundment	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd3/gal)	Source Area (ft2)	269.50	750.00
e. Source Volume/Area Value		1.08E+02	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		1.08E+02	

Source Hazardous Substances	Depth (feet)	Liquid	Concent.	Units
Pentachlorophenol	< 2	YES	0.0E+00	ppm
Phenol	< 2	YES	0.0E+00	ppm

Documentation for Source Type:

Pond C is a surface impoundment with no liner used as the final separating pond (Ref.2, p. 13).

Reference: 2

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

Documentation for Source Hazardous Substances:

A water sample was collected directly from Pond C on December 15, 1980 at 1615 hours. Pentachlorophenol and total phenols were detected in this water sample #1, but no background samples were collected (Ref. 9). There were three additional soil/sediment samples collected on December 15, 1980 (Ref. 2, p. 017 and 018). Missing from the files is page two of Reference 9 that includes samples 3 and 4.

Reference: 2, 9

Documentation for Source Volume:

The dimensions of Pond C are 50 ft x 15 ft and 10 ft deep (Ref. 2, p. 13).

Convert to yards: $50 \text{ ft} \times \frac{0.33 \text{ yds}}{1 \text{ ft}} = 16.5 \text{ yds}$

$$15 \text{ ft} \times \frac{0.33 \text{ yds}}{1 \text{ ft}} = 4.95 \text{ yds}$$
$$10 \text{ ft} \times \frac{0.33 \text{ yds}}{1 \text{ ft}} = 3.3 \text{ yds}$$
$$16.5 \text{ yds} \times 4.95 \text{ yds} \times 3.3 \text{ yds} = 269.52 \text{ cubic yards}$$

Reference: 2

Documentation for Source Area:

The area of Pond C is 50 ft by 15 ft (Ref.2,p. 13).

Reference: 2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Pond D

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID		Pond D	
b. Source Type		Surface Impoundment	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd ³ /gal)	Source Area (ft ²)	449.20	1250.00
e. Source Volume/Area Value		1.80E+02	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		1.80E+02	

Documentation for Source Type:

Pond D is a surface impoundment use to store stormwater (Ref. 2, p. 14).

Reference: 2

Documentation for Source Volume:

The dimensions of Pond D are 50 ft x 25 ft and 10 ft deep (Ref. 2, 14).

Convert to yards: 50 ft x 0.33 yds = 16.5 yds
1 ft

$$\begin{array}{r} 25 \text{ ft} \times 0.33 \text{ yds} = 8.25 \text{ yds} \\ 1 \text{ ft} \end{array}$$

$$\begin{array}{r} 10 \text{ ft} \times 0.33 \text{ yds} = 3.3 \text{ yds} \\ 1 \text{ ft} \end{array}$$

$$16.5 \text{ yds} \times 8.25 \text{ yds} \times 3.3 \text{ yds} = 449.21 \text{ cubic yards}$$

Reference: 2

Documentation for Source Area:

The area of Pond D is 50 ft x 25 ft (Ref.2, p. 14).

Reference: 2

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE: Storage Tank

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID		Storage Tank	
b. Source Type		Non-Drum Container	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd3/gal)	Source Area (ft2)	1440.00	0.00
e. Source Volume/Area Value		5.76E+02	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		5.76E+02	

Documentation for Source Type:

This source consists of 5 storage tanks (Ref. 2, p. 15).

Reference: 2

Documentation for Source Volume:

The estimated number and capacity of storage tanks are 5 - 40,000 cubic feet total capacity (Ref.2, p. 15).

Convert to cubic yards: $40,000 \text{ ft}^3 \times 0.036 \text{ yds}^3 = 1440 \text{ yds}^3$

Reference: 2

1. WASTESTREAM QUANTITY SUMMARY TABLE, SOURCE:

a. Wastestream ID	
b. Hazardous Constituent Quantity (C) (lbs.)	0.00
c. Data Complete?	NO
d. Hazardous Wastestream Quantity (W) (lbs.)	0.00
e. Data Complete?	NO
f. Wastestream Quantity Value (W/5,000)	0.00E+00

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

2. SOURCE HAZARDOUS WASTE QUANTITY FACTOR TABLE

a. Source ID			
b. Source Type		Drums	
c. Secondary Source Type		N.A.	
d. Source Vol. (yd3/gal)	Source Area (ft2)	0.00	0.00
e. Source Volume/Area Value		0.00E+00	
f. Source Hazardous Constituent Quantity (HCQ) Value (sum of 1b)		0.00E+00	
g. Data Complete?		NO	
h. Source Hazardous Wastestream Quantity (WSQ) Value (sum of 1f)		0.00E+00	
i. Data Complete?		NO	
k. Source Hazardous Waste Quantity (HWQ) Value (2e, 2f, or 2h)		0.00E+00	

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

3. SITE HAZARDOUS WASTE QUANTITY SUMMARY

No.	Source ID	Migration Pathways	Vol. or Area Value (2e)	Constituent or Wastestream Value (2f,2h)	Hazardous Waste Qty. Value (2k)
1	Pond A (Separation)	GW-SW-SE-A	9.20E+02	0.00E+00	9.20E+02
2	Pond B	GW-SW-SE-A	1.35E+02	0.00E+00	1.35E+02
3	Pond C	GW-SW-SE-A	1.08E+02	0.00E+00	1.08E+02
4	Pond D	GW-SW-SE-A	1.80E+02	0.00E+00	1.80E+02
5	Storage Tank	GW-SW-SE-A	5.76E+02	0.00E+00	5.76E+02
6			0.00E+00	0.00E+00	0.00E+00

WASTE QUANTITY

Thomason Lumber Company - 07/22/94

4. PATHWAY HAZARDOUS WASTE QUANTITY AND WASTE CHARACTERISTICS SUMMARY TABLE

Migration Pathway	Contaminant Values	HWQVs*	WCVs**
Ground Water	Toxicity/Mobility 1.00E+00	100	3
SW: Overland Flow, DW	Tox./Persistence 1.00E+02	100	10
SW: Overland Flow, HFC	Tox./Persis./Bioacc. 5.00E+04	100	32
SW: Overland Flow, Env	Etox./Persis./Bioacc. 5.00E+05	100	56
SW: GW to SW, DW	Tox./Persistence 1.00E+00	100	3
SW: GW to SW, HFC	Tox./Persis./Bioacc. 5.00E+02	100	10
SW: GW to SW, Env	Etox./Persis./Bioacc. 5.00E+02	100	10
Soil Exposure:Resident	Toxicity 1.00E+02	100	10
Soil Exposure: Nearby	Toxicity 1.00E+02	100	10
Air	Toxicity/Mobility 2.00E+00	100	3

* Hazardous Waste Quantity Factor Values

** Waste Characteristics Factor Category Values

Note: SW = Surface Water
 GW = Ground Water
 DW = Drinking Water Threat
 HFC = Human Food Chain Threat
 Env = Environmental Threat

No. Aquifer ID	Type	Overlaying No.	Inter-Connected with	Likelihood of Release	Targets
1	Non K	0	0	430	0.00E+00

Containment

No.	Source ID	HWQ Value	Containment Value
1	Pond A (Separation)	9.20E+02	10
2	Pond B	1.35E+02	10
3	Pond C	1.08E+02	10
4	Pond D	1.80E+02	10
5	Storage Tank	5.76E+02	10

=====
Containment Factor 10

Documentation for Ground Water Containment, Source Pond A (Separation):

Pond A is an unlined surface impoundment for separating PCP and Creosote (Ref. 2 p. 11).

Reference: 2

Documentation for Ground Water Containment, Source Pond B:

Pond B is a surface impoundments filled with saw dust to act as a filter aid. This surface impoundment has no liner (Ref. 2 p. 12).

Reference: 2

Documentation for Ground Water Containment, Source Pond C:

Pond C is the final surface impoundment that discharges down the slope to a nearby intermittent creek. The surface impoundment does not have a liner (Ref. 2 p. 13 and 18).

Reference: 2

Documentation for Ground Water Containment, Source Pond D:

Pond D is accumulated storm water. This surface impoundment has no liner (Ref. 2, p. 14).

Reference: 2

Documentation for Ground Water Containment, Source Storage Tank:

There is evidence of overflow that was documented from the separator tank (Ref. 2 p. 15).

Reference: 2

Net Precipitation

Net Precipitation (inches)

6

Documentation for Net Precipitation:

Used HRS Figure 3-2 to enter net precipitation data (Ref.1).

Reference: 1

Aquifer:

Type of Aquifer: Non Karst

Overlaying Aquifer: 0

Interconnected with: 0

Documentation for Aquifer:

Groundwater pathway was not evaluated because groundwater is not used for drinking water in the vicinity of the site (Ref. 15).

Reference: 15

OBSERVED RELEASE

No.	Well ID	Well Type	Distance (miles)	Level of Contamination
- N/A and/or data not specified				

=====

Observed Release Factor	0
-------------------------	---

POTENTIAL TO RELEASE

Containment

Containment Factor 10

Net Precipitation

Net Precipitation Factor 3

Depth to Aquifer

A. Depth of Hazardous Substances 0.00 feet

B. Depth to Aquifer from Surface 0.00 feet

C. Depth to Aquifer (B - A) 0.00 feet

Depth to Aquifer Factor 5

Travel Time

Are All Layers Karst? NO

Thickness of Layer(s) with Lowest Conductivity 0.00 feet

Hydraulic Conductivity (cm/sec) 0.0E-00

Travel Time Factor 35

=====
Potential to Release Factor 430

Source: 1 Pond A (Separation)

Source Hazardous Waste Quantity Value: 920.00

Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	-------------------	--------------------------------

Source: 2 Pond B

Source Hazardous Waste Quantity Value: 134.76

Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	-------------------	--------------------------------

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
Pentachlorophenol	100	1.00E-02	1.00E+00
Phenol	1	1.00E+00	1.00E+00

Source: 4 Pond D

Source Hazardous Waste Quantity Value: 179.68

Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	-------------------	--------------------------------

Source: 5 Storage Tank

Source Hazardous Waste Quantity Value: 576.00

Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	-------------------	--------------------------------

Hazardous Substances Found in an Observed Release

Well No.	Observed Release Hazardous Substance	Toxicity Value	Mobility Value	Toxicity/ Mobility Value
-------------	---	-------------------	-------------------	--------------------------------

- N/A and/or data not specified

Toxicity/Mobility Value from Source Hazardous Substances:	1.00E+00
Toxicity/Mobility Value from Observed Release Hazardous Substances:	0.00E+00
Toxicity/Mobility Factor:	1.00E+00
Sum of Source Hazardous Waste Quantity Values:	1.92E+03
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	3

Population by Well

No.	Well ID	Sample Type	Distance (miles)	Level of Contamination	Population
<hr/>					
- N/A and/or data not specified					

Level I Population Factor: 0.00

Level II Population Factor: 0.00

Potential Contamination by Distance Category

Distance Category (miles)	Population	Value
> 0 to 1/4	0.0	0.00E+00
> 1/4 to 1/2	0.0	0.00E+00
> 1/2 to 1	0.0	0.00E+00
> 1 to 2	0.0	0.00E+00
> 2 to 3	0.0	0.00E+00
> 3 to 4	0.0	0.00E+00

Potential Contamination Factor: 0.000

Nearest Well

Level of Contamination: N.A.

Nearest Well Factor: 0.00E+00

Resources

Resource Use: NO

Resource Factor: 0.00E+00

Wellhead Protection Area

No wellhead protection area

Wellhead Protection Area Factor: 0.00E+00

PREscore 2.0 - PRESCORE.TCL File 05/11/93
SURFACE WATER PATHWAY SEGMENT SUMMARY
Thomason Lumber Company - 07/22/94

PAGE: 40

No. Segment ID	Segment Type	Water Type	Start Point (mi)	End Point (mi)	Average Flow (cfs)
1 Yanubbee Creek	River	Fresh	0.00	7.00	100
2 Little River	River	Fresh	7.00	15.00	1660

Documentation for segment: Yanubbee Creek:

Surface water flows in an intermittant creek approximately 1.8 miles southeast before discharging into Yanubbee Creek. Yanubbee Creek flows approximately 7 miles before discharging into Little River (Ref.8).

Reference: 8

Documentation for segment: Little River:

Yanubbee flows approximately 7 miles before discharging into the Little River. The remainder of the surface water pathway is in the Little River(Ref.8). Approximately 5 miles southwest from the site, annual mean discharges were regulated from 1969 - 1984 (Ref. 5, p. 380).

Reference: 5,8

OBSERVED RELEASE

No. Sample ID	Sample Type	Distance (miles)	Level of Contamination DW HFC Env
---------------	-------------	---------------------	--------------------------------------

- N/A and/or data not specified

=====

Observed Release Factor	0
-------------------------	---

POTENTIAL TO RELEASE

Potential to Release by Overland Flow

Containment

No.	Source ID	HWQ Value	Containment Value
1	Pond A (Separation)	9.20E+02	10
2	Pond B	1.35E+02	10
3	Pond C	1.08E+02	10
4	Pond D	1.80E+02	10
5	Storage Tank	5.76E+02	10

=====
Containment Factor: 10

Documentation for Overland Flow Containment, Source Pond A (Separation):

Pond A has free liquids present with some instability and erosion of embankments observed and no liner (Ref.2 p.1).

Reference: 2

Documentation for Overland Flow Containment, Source Pond B:

Pond B has no embankments and erosion has been observed in the pond area (Ref. 2 p. 12 and Ref. 1 Table 4-2).

Reference: 1, 2

Documentation for Overland Flow Containment, Source Pond C:

Pond C has free liquids present with no liner, no embankments and erosion observed (Ref. 2, p. 13).

Reference: 1, 2

Documentation for Overland Flow Containment, Source Pond D:

Free liquids are present in Pond D, which no liner , no embankments, and erosion along the sides (Ref. 2, p.14).

Reference: 2

Documentation for Overland Flow Containment, Source Storage Tank:

There is evidence of overflow from the separator tank (Ref. 2, p.15).

Reference: 2

Distance to Surface Water

Distance to Surface Water: 1.8 feet
Distance to Surface Water Factor: 25

Documentation for Distance to Surface Water:

Surface water is located approximately 1.8 miles southeast of the site (Ref. 8, p. 01).

Reference: 8

Runoff

A. Drainage Area: 50.0 acres

Documentation for Drainage Area:

The drainage area for the site is assumed to be 50 acres (Ref.8 p.002).

Reference: 8 (p. 002)

B. 2-year, 24-hour Rainfall: 4.0 inches

Documentation for Rainfall:

The 2-year 24-hour rainfall for this area is 4 inches (Ref.4, p.2)

Reference: 2

C. Soil Group: B
Medium-textured soils with moderate infiltration rates

Documentation for Soil Group:

The soil underneath the site consists of 10% sand, 60% clay, and 30% gravel. It has a moderate permeability rate (Ref.2, p. 9).

Reference: 2

Runoff Factor: 2

=====

Potential to Release by Overland Flow Factor: 270

Potential to Release by Flood

No.	Source ID	HWQ Value	Flood Containment Value	Flood Frequency Value	Potential to Release by Flood
1	Pond A (Separation)	9.20E+02	10	25	250
2	Pond B	1.35E+02	10	25	250
3	Pond C	1.08E+02	10	25	250
4	Pond D	1.80E+02	10	25	250
5	Storage Tank	5.76E+02	10	25	250

=====
Potential to Release by Flood Factor: 250

Documentation for Flood Containment, Source Pond A (Separation):

Not contained for any flood (Ref.1 table 4-8).

Reference: 1

Documentation for Flood Frequency, Source Pond A (Separation):

The site is located adjacent to an intermittent creek and is assumed to be located within the 100-year flood plain (Ref.8, p. 02).

Reference: 2

Documentation for Flood Containment, Source Pond B:

It is not specified whether the surface impoundment is contained for all floods, but there is no freeboard left during a site inspection (Ref. 2 p. 12).

Reference: 2

Documentation for Flood Frequency, Source Pond B:

The site is located adjacent to an intermittent creek and is assumed to be located within the 100-year flood plain (Ref.8 p.02)

Reference: 8

Documentation for Flood Containment, Source Pond C:

There is no mention of containing against floods. There is an estimated freeboard of 0 to 0.5 feet (Ref.2 p. 13).

Reference: 2

Documentation for Flood Frequency, Source Pond C:

The site is located next to an intermittent creek and is assumed to be within the 100-year flood plain (Ref. 8, p.02).

Reference: 8

Documentation for Flood Containment, Source Pond D:

The surface impoundment is not contained for any floods. Erosion was observed around ponds where slope is steep (Ref. 2, p. 14).

Reference: 2

Documentation for Flood Frequency, Source Pond D:

The site is located adjacent to an intermittent creek and is assumed to be located in the 100-year flood plain (Ref. 8, p.02).

Reference: 8

Documentation for Flood Containment, Source Storage Tank:

There is no documentation whether source is contained against floods (Ref.1, Table 4-8).

Reference: 1

Documentation for Flood Frequency, Source Storage Tank:

The site is located adjacent to an intermittent creek and is assumed to within the 100-year flood plain (Ref. 8, p. 2)

Reference: 8

Source: 1 Pond A (Separation)

Source Hazardous Waste Quantity Value: 920.00

Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
---------------------	-------------------	----------------------	-----------------------------------

Source: 2 Pond B

Source Hazardous Waste Quantity Value: 134.76

Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
---------------------	-------------------	----------------------	-----------------------------------

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
Pentachlorophenol	100	1.00E+00	1.00E+02
Phenol	1	1.00E+00	1.00E+00

Source: 4 Pond D

Source Hazardous Waste Quantity Value: 179.68

Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
---------------------	-------------------	----------------------	-----------------------------------

Source: 5 Storage Tank

Source Hazardous Waste Quantity Value: 576.00

Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
---------------------	-------------------	----------------------	-----------------------------------

Hazardous Substances Found in an Observed Release

Sample No.	Observed Release Hazardous Substance	Toxicity Value	Persistence Value	Toxicity/ Persistence Value
------------	---	-------------------	----------------------	-----------------------------------

- N/A and/or data not specified

Toxicity/Persistence Value from Source Hazardous Substances:	1.00E+02
Toxicity/Persistence Value from Observed Release Hazardous Substances:	0.00E+00
Toxicity/Persistence Factor:	1.00E+02
Sum of Source Hazardous Waste Quantity Values:	1.92E+03
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	10

Level I Concentrations

- N/A and/or data not specified

Level II Concentrations

- N/A and/or data not specified

Most Distant Level I Sample

- N/A and/or data not specified

Most Distant Level II Sample

- N/A and/or data not specified

Level I Concentrations

Intake	Distance Along the In-water Segment from the Probable Point of Entry (miles)	Population
--------	--	------------

- N/A and/or data not specified

=====
 Population Served by Level I Intakes: 0.0

Level I Population Factor: 0.00E+00

Level II Concentrations

Intake	Distance Along the In-water Segment from the Probable Point of Entry (miles)	Population
--------	--	------------

- N/A and/or data not specified

=====

Population Served by Level II Intakes:

0.0

Level II Population Factor: 0.00E+00

Potential Contamination

Intake ID	Average Annual Flow (cfs)	Population Served
- N/A and/or data not specified		

Documentation for Intake :

The population of Broken Bow (3,965 people) receives their drinking water from Mountain Fork River (Ref. 7, p. 001). Mountain Fork River is located approximately 8 miles notheast of the site and is not located along the surface water pathway (Ref. 7, p. 001; Ref. 8).

Reference: 7, 8

Type of Surface Water Body	Total Population	Dilution-Weighted Population
- N/A and/or data not specified		

=====

Dilution-Weighted Population Served
 by Potentially Contaminated Intakes: 0.0

Potential Contamination Factor: 0.0

Nearest Intake

Location of Nearest Drinking Water Intake: N.A.

Nearest Intake Factor: 0.00

Resources

Resource Use: NO

Resource Value: 0.00E+00

Documentation for Resources:

No resources identified

Reference:

Source: 1 Pond A (Separation)

Source Hazardous Waste Quantity Value: 920.00

Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
<hr/>				

Source: 2 Pond B

Source Hazardous Waste Quantity Value: 134.76

Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
<hr/>				

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
Pentachlorophenol	100	1.00E+00	5.00E+02	5.00E+04
Phenol	1	1.00E+00	5.00E+00	5.00E+00

Source: 4 Pond D

Source Hazardous Waste Quantity Value: 179.68

Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
<hr/>				

Source: 5 Storage Tank

Source Hazardous Waste Quantity Value: 576.00

Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
<hr/>				

Hazardous Substances Found in an Observed Release

Sample No.	Observed Release Hazardous Substance	Toxicity Value	Persistence Value	Bio- accum. Value	Toxicity/ Persistence/ Bioaccum. Value
------------	---	-------------------	----------------------	-------------------------	---

- N/A and/or data not specified

Toxicity/Persistence/Bioaccumulation Value from Source Hazardous Substances:	5.00E+04
Toxicity/Persistence/Bioaccumulation Value from Observed Release Hazardous Substances:	0.00E+00
Toxicity/Persistence/Bioaccumulation Factor:	5.00E+04
Sum of Source Hazardous Waste Quantity Values:	1.92E+03
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	32

Level I Concentrations

- N/A and/or data not specified

Level II Concentrations

- N/A and/or data not specified

Most Distant Level I Sample

- N/A and/or data not specified

Most Distant Level II Sample

- N/A and/or data not specified

Level I Concentrations

Fishery	Annual Production (pounds)	Human Food Chain Population Value
---------	-------------------------------	--------------------------------------

- N/A and/or data not specified

=====

Sum of Human Food Chain Population Values: 0.00E+00

Level I Concentrations Factor: 0.00E+00

Level II Concentrations

Fishery	Annual Production (pounds)	Human Food Chain Population Value
- N/A and/or data not specified		

=====

Sum of Human Food Chain Population Values: 0.00E+00

Level II Concentrations Factor: 0.00E+00

Potential Contamination

Fishery	Annual Production (pounds)	Type of Surface Water Body	Average Annual Flow (cfs)	Pop. Value (Pi)	Dilution Weight (Di)	Pi*Di
2 Little River	1.0	River	1660	0.0	1.00E-03	3.00E-05

Sum of (Pi*Di): 3.00E-05

Potential Human Food Chain Contamination Factor: 3.00E-06

Documentation for Little River Fishery:

The state of Oklahoma does not keep fish production records(Ref. 17). According to the HRS Guidance Manual, an estimate of 1 pound per year can be used if actual or surragate data is unavailable, provided that it has been documented that people do fish in the surface water. (Ref. 18, p. 315)

People do fish in the Little River. The types of fish caught for human consumption are large-mouth bass, channel catfish, and blue gill fishes (Ref.17).

Reference: 17, 18 (P. 315)

Food Chain Individual

Location of Nearest Fishery: Little River
 Distance from the Probable Point of Entry: 7.00 miles
 Type of Surface Water Body: River
 Dilution Weight: 0.0010000
 Level of Contamination: Potential

Food Chain Individual Factor: 0.00

Documentation for Little River:

Yanubee flows approximately 7 miles before discharging into the Little River. The remainder of the surface water pathway is in the Little River(Ref.8). Approximately 5 miles southwest from the site, annual mean discharges were regulated from 1969 - 1984 (Ref. 5, p. 380).

Reference: 5,8

Source: 1 Pond A (Separation)

Source Hazardous Waste Quantity Value: 920.00

Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
---------------------	---------------------------	----------------------	-------------------------	--

Source: 2 Pond B

Source Hazardous Waste Quantity Value: 134.76

Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
<hr/>				

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
Pentachlorophenol	100	1.00E+00	5.00E+03	5.00E+05
Phenol	10000	1.00E+00	5.00E+00	5.00E+04

Source: 4 Pond D

Source Hazardous Waste Quantity Value: 179.68

Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
<hr/>				

Source: 5 Storage Tank

Source Hazardous Waste Quantity Value: 576.00

Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
---------------------	---------------------------	----------------------	-------------------------	--

Hazardous Substances Found in an Observed Release

Sample No.	Observed Release Hazardous Substance	Eco- toxicity Value	Persistence Value	Bio- accum. Value	Ecotoxicity/ Persistence/ Bioaccum. Value
------------	---	---------------------------	----------------------	-------------------------	--

- N/A and/or data not specified

Ecotoxicity/Persistence/Bioaccummulation Value from Source Hazardous Substances:	5.00E+05
Ecotoxicity/Persistence/Bioaccummulation Value from Observed Release Hazardous Substances:	0.00E+00
Ecotoxicity/Persistence/Bioaccummulation Factor:	5.00E+05
Sum of Source Hazardous Waste Quantity Values:	1.92E+03
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	56

Level I Concentrations

- N/A and/or data not specified

Level II Concentrations

- N/A and/or data not specified

Most Distant Level I Sample

- N/A and/or data not specified

Most Distant Level II Sample

- N/A and/or data not specified

Level I Concentrations

Sensitive Environment	Distance from Probable Point of Entry to Sensitive Env. (miles)	Sensitive Environment Value
- N/A and/or data not specified		

Sum of Sensitive Environments Values: 0

Wetlands

Wetland	Distance from Probable Point of Entry to Wetland (miles)	Wetlands Frontage (miles)
- N/A and/or data not specified		

Total Wetlands Frontage: 0.00 Miles Total Wetlands Value: 0

=====

Sum of Sensitive Environments Value + Wetlands Value: 0.00E+00

Level I Concentrations Factor: 0.00E+00

Level II Concentrations

Sensitive Environment	Distance from Probable Point of Entry to Sensitive Env. (miles)	Sensitive Environment Value
- N/A and/or data not specified		

Sum of Sensitive Environments Values: 0

Wetlands

Wetland	Distance from Probable Point of Entry to Wetland (miles)	Wetlands Frontage (miles)
- N/A and/or data not specified		

Total Wetlands Frontage: 0.00 Miles Total Wetlands Value: 0

=====

Sum of Sensitive Environments Value + Wetlands Value: 0.00E+00

Level II Concentrations Factor: 0.00E+00

Potential Contamination

Sensitive Environments

Type of Surface Water Body	Sensitive Environment	Sensitive Environment Value
-------------------------------	-----------------------	-----------------------------------

Wetlands

Type of Surface Water Body	Sensitive Environment	Wetlands Frontage	Wetlands Value
River	1 Wetlands	15.00	350

Documentation for Sensitive Environment Wetlands:

No known sensitive environment is located in a 4-mile radius of the site (Ref.10). Based on review of topographic maps, 15 miles of wetland frontage were assumed to be present in along the surface water pathway (Ref. 8).

Reference: 8, 10 (p. 002)

Type of Surface Water Body	Sum of Sens. Environment Values (Sj)	Sum of Wetland Frontage Values (Wj)	Dilution Weight (Dj)	Dj (Wj+Sj)
Small to Moderate Stream	0	350	1.00E-01	3.50E+01

Sum of Dj (Wj+Sj): 3.50E+01
 Sum of Dj (Wj+Sj)/10: 3.50E+00

=====
 Potential Contamination Sensitive Environment Factor: 4.00E+00

Likelihood of Exposure

No. Source ID Level of Contamination

3	Pond C	Level II
---	--------	----------

Likelihood of Exposure Factor: 550

Documentation for Area of Contamination, Source Pond C:

Reference: 2

Source No.	Hazardous Substance	Depth (ft.)	Concent.	Cancer	RFD	Units
3	Pentachlorophenol	< 2	0.0E+00	4.9E+00	1.7E+04	ppm
3	Phenol	< 2	0.0E+00	0.0E+00	3.5E+05	ppm

Documentation for Source Pond C, Contaminants:

A water sample was collected directly from Pond C on December 15, 1980 at 1615 hours. Pentachlorophenol and total phenols were detected in this water sample #1, but no background samples were collected (Ref. 9). There were three additional soil/sediment samples collected on December 15, 1980 (Ref. 2, p. 017 and 018). Missing from the files is page two of Reference 9 that includes samples 3 and 4.

Reference: 2, 9

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value
Pentachlorophenol	100
Phenol	1

Toxicity Factor:	1.00E+02
Sum of Source Hazardous Waste Quantity Values:	1.08E+02
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	10

Targets

Level I Population:	0.0	Value:	0.00
Level II Population:	0.0	Value:	0.00
Workers:	10.0	Value:	5.00

Documentation for Workers:

There are approximately 10 people on-site (Ref. 6 p.8).

Reference: 6

Resident Individual:	Potentia	Value:	0.00
Resources:	NO	Value:	0.00

Documentation for Resources:

No resources identified.

Reference: 2

Terrestrial Sensitive Environment	Value
-----------------------------------	-------

- N/A and/or data not specified

=====

Terrestrial Sensitive Environments Factor: 0.00

Likelihood of Exposure

No. Source ID	Level of Contamination	Attractiveness/ Accessibility	Area of Contam. (sq. feet)
3 Pond C	Level II	10	750
Highest Attractiveness/Accessibility Value: 10			
Sum of Eligible Areas Of Contamination (sq. feet):			750
Area of Contamination Value: 5			

Likelihood of Exposure Factor Category: 5

Documentation for Attractiveness/Accessibility, Source Pond A (Separation):

The site does not have a fence (Ref.2 p.7).

Reference: 2

Documentation for Attractiveness/Accessibility, Source Pond B:

The site is not surrounded by a fence (Ref. 2, p.7). Site is assumed no to have any public recreation use.

Reference: 2

Documentation for Attractiveness/Accessibility, Source Pond C:

There site is not surrounded by a fence (Ref. 2 p.7).

Reference: 2

Documentation for Attractiveness/Accessibility, Source Pond D:

The site is not fenced (Ref. 2 p. 7).

Reference: 2

Documentation for Attractiveness/Accessibility, Source Storage Tank:

The site is not fenced (Ref. 2, p.7).

Reference: 2

Source Hazardous Substance No.		Depth (ft.)	Concent.	Cancer	RFD	Units
3	Pentachlorophenol	< 2	0.0E+00	4.9E+00	1.7E+04	ppm
3	Phenol	< 2	0.0E+00	0.0E+00	3.5E+05	ppm

Documentation for Source Pond C, Contaminants:

A water sample was collected directly from Pond C on December 15, 1980 at 1615 hours. Pentachlorophenol and total phenols were detected in this water sample #1, but no background samples were collected (Ref. 9). There were three additional soil/sediment samples collected on December 15, 1980 (Ref. 2, p. 017 and 018). Missing from the files is page two of Reference 9 that includes samples 3 and 4.

Reference: 2, 9

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value
Pentachlorophenol	100
Phenol	1

Toxicity Factor:	1.00E+02
Sum of Source Hazardous Waste Quantity Values:	1.08E+02
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	10

Nearby Individual

Population within 1/4 mile: 327.0

Nearby Individual Value: 1.0

Population Within 1 Mile

Travel Distance Category	Number of People	Value
> 0 to 1/4 mile	327.0	1.3
> 1/4 to 1/2 mile	901.0	0.7
> 1/2 to 1 mile	1987.0	1.0

Population Within 1 Mile Factor: 3.0

Documentation for Population > 0 to 1/4 mile Distance Category:

There are approximately 327 people in the 0 to 1/4 mile target distance category (Ref. 3,p. 02).

Reference: 3

Documentation for Population > 1/4 to 1/2 mile Distance Category:

There are approximately 901 people in the 1/4 to 1/2 mile target distance limit (Ref. 3, p. 02).

Reference: 3

Documentation for Population > 1/2 to 1 mile Distance Category:

There are approximately 1987 people in the 1/2 to 1 mile target distance category (Ref. 3, p. 02).

Reference: 3

OBSERVED RELEASE

No. Sample ID	Distance (miles)	Level of Contamination
---------------	---------------------	------------------------

- N/A and/or data not specified

=====

Observed Release Factor: 0

Gas Migration Potential

GAS POTENTIAL TO RELEASE

Source ID	Source Type	Gas Contain. Value (A)	Gas Source Type Value (B)	Gas Migrtn. Potent. Value (C)	Sum (B+C)	Gas Potential to Rel. Value A(B+C)
Pond C	Surface Impoundment	10	28	11	39	390

Gas Potential to Release Factor: 390

Documentation for Gas Containment, Source Pond A (Separation):

A value of 10 was assigned because, there is no situation that is specifically listed in HRS Table 6-3.

Reference: 1

Documentation for Source Type, Source Pond A (Separation):

Pond A is an unlined surface impoundment with demensions of approximatly 80 feet by 80 feet by 10 feet (Ref.2 p.11).

Reference: 2

Documentation for Gas Containment, Source Pond B:

Pond B was assigned a value of 10 because, there is no specifically listed situation in Table 6-3 (Ref. 1, Table 6-3).

Reference: 1

Documentation for Source Type, Source Pond B:

Pond B is a surface impoundment filled with sawdust to act as filter aid (Ref.2, p. 12).

Reference: 2

Documentation for Gas Containment, Source Pond C:

There is no situation listed in HRS Table 6-3 that specifically describes Pond C (Ref.1 Table 6-3).

Reference: 1

Documentation for Source Type, Source Pond C:

Pond C is a surface impoundment with no liner used as the final separating pond (Ref.2, p. 13).

Reference: 2

Documentation for Gas Containment, Source Pond D:

Pond D was assigned a value of 10 because, there was no situation specifically listed on HRS Table 6-3 (Ref.1 Table 6-3).

Reference: 1

Documentation for Source Type, Source Pond D:

Pond D is a surface impoundment use to store stormwater (Ref. 2, p. 14).

Reference: 2

Documentation for Gas Containment, Source Storage Tank:

No situation was specifically listed in HRS Table 6-3, so a containment value of 10 was assigned (Ref. 1, Table 6-3).

Reference: 1

Documentation for Source Type, Source Storage Tank:

This source consists of 5 storage tanks (Ref. 2, p. 15).

Reference: 2

Source: Pond A (Separation)

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
-----------------------------	--

Average of Gas Migration Potential Value for 3 Hazardous Substances: 0.000
=====

Gas Migration Potential Value From Table 6-7: 0

Source: Pond B

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
-----------------------------	--

Average of Gas Migration Potential Value for 3 Hazardous Substances: 0.000
=====

Gas Migration Potential Value From Table 6-7: 0

Source: Pond C

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
Pentachlorophenol	6
Phenol	11

Average of Gas Migration Potential Value for 3 Hazardous Substances: 8.500

=====

Gas Migration Potential Value From Table 6-7: 11

Source: Pond D

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
-----------------------------	--

Average of Gas Migration Potential Value for 3 Hazardous Substances: 0.000
=====

Gas Migration Potential Value From Table 6-7: 0

Source: Storage Tank

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
-----------------------------	--

Average of Gas Migration Potential Value for 3 Hazardous Substances: 0.000
=====

Gas Migration Potential Value From Table 6-7: 0

Source:

Gaseous Hazardous Substance	Hazardous Substance Gas Migration Potential Value
-----------------------------	--

Average of Gas Migration Potential Value for 3 Hazardous Substances: 0.000
=====

Gas Migration Potential Value From Table 6-7: 0

Particulate Migration Potential

PARTICULATE POTENTIAL TO RELEASE

Source ID	Source Type	Partic. Contain. Value (A)	Partic. Source Type Value (B)	Partic. Migrtn. Potent. Value (C)	Sum (B+C)	Partic. Potential to Rel. Value A(B+C)
Pond C	Surface Impoundment	10	0	11	11	110

Particulate Potential to Release Factor: 110

Documentation for Particulate Containment, Source Pond A (Separation):

A value of 10 was assigned from HRS Table 6-9, because no situation was specifically listed (Ref.1 Table 6-9).

Reference: 1

Documentation for Source Type, Source Pond A (Separation):

Pond A is an unlined surface impoundment with demensions of approximatly 80 feet by 80 feet by 10 feet (Ref.2 p.11).

Reference: 2

Documentation for Particulate Containment, Source Pond B:

A value of 10 was assigned to Pond B, because there were no situations specically listed in HRS Table 6-9 (Ref. 1, Table 6-9).

Reference: 1

Documentation for Source Type, Source Pond B:

Pond B is a surface impoundment filled with sawdust to act as filter aid (Ref.2, p. 12).

Reference: 2

Documentation for Particulate Containment, Source Pond C:

Pond C did not have a situation specifically listed in HRS Table 6-9, therefore a value of 10 was assigned (Ref. 1 Table 6-9).

Reference: 1

Documentation for Source Type, Source Pond C:

Pond C is a surface impoundment with no liner used as the final separating pond (Ref.2, p. 13).

Reference: 2

Documentation for Particulate Containment, Source Pond D:

Pond D is assumed to contain only liquids (Ref. 2 P. 14). Assigned a value of 0 from HRS Table 6-9 (Ref. 1, Table 6-9).

Reference: 1, 2

Documentation for Source Type, Source Pond D:

Pond D is a surface impoundment use to store stormwater (Ref. 2, p. 14).

Reference: 2

Documentation for Particulate Containment, Source Storage Tank:

The storage tanks assumed to only contain liquids and not particulates(Ref.1 Table 6-9).

Reference: 1

Documentation for Source Type, Source Storage Tank:

This source consists of 5 storage tanks (Ref. 2, p. 15).

Reference: 2

Documentation for Particulate Migration Potential:

Particulate migration factor value assigned from the HRS Figure 6-2 (Ref. 1).

Reference: 1

Source: Pond A (Separation)

Particulate Hazardous Substance

Source: Pond B

Particulate Hazardous Substance

Source: Pond C

Particulate Hazardous Substance

Pentachlorophenol

Source: Pond D

Particulate Hazardous Substance

Source: Storage Tank

Particulate Hazardous Substance

Source:

Particulate Hazardous Substance

Source: 1 Pond A (Separation)

Source Hazardous Waste Quantity Value: 920.00

Hazardous Substance	Toxicity Value	Gas Mobility Value	Particulate Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	--------------------------	----------------------------------	--------------------------------

Source: 2 Pond B

Source Hazardous Waste Quantity Value: 134.76

Hazardous Substance	Toxicity Value	Gas Mobility Value	Particulate Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	--------------------------	----------------------------------	--------------------------------

Source: 3 Pond C

Source Hazardous Waste Quantity Value: 107.80

Hazardous Substance	Toxicity Value	Gas Mobility Value	Particulate Mobility Value	Toxicity/ Mobility Value
Pentachlorophenol	100	2.00E-02	8.00E-04	2.00E+00
Phenol	1	1.00E+00	NA	1.00E+00

Source: 4 Pond D

Source Hazardous Waste Quantity Value: 179.68

Hazardous Substance	Toxicity Value	Gas Mobility Value	Particulate Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	--------------------------	----------------------------------	--------------------------------

Source: 5 Storage Tank

Source Hazardous Waste Quantity Value: 576.00

Hazardous Substance	Toxicity Value	Gas Mobility Value	Particulate Mobility Value	Toxicity/ Mobility Value
---------------------	-------------------	--------------------------	----------------------------------	--------------------------------

Hazardous Substances Found in an Observed Release

Sample ID	Observed Release Hazardous Substance	Particulate Toxicity/ Mobility Value	Gas Toxicity/ Mobility Value
-----------	---	--	------------------------------------

- N/A and/or data not specified

Documentation for Particulate Mobility:

Particulate mobility value assigned from HRS Figure 6-3 (Ref. 1)

Reference: 1

Toxicity/Mobility Value from Source Hazardous Substances:	2.00E+00
Toxicity/Mobility Value from Observed Release Hazardous Substances:	0.00E+00
Toxicity/Mobility Factor:	2.00E+00
Sum of Source Hazardous Waste Quantity Values:	1.92E+03
Hazardous Waste Quantity Factor:	100
Waste Characteristics Factor Category:	3

AIR PATHWAY TARGETS

Thomason Lumber Company - 07/22/94

Actual Contamination

No. Sample ID	Distance (miles)	Level of Contamination
---------------	---------------------	------------------------

- N/A and/or data not specified

Potential ContaminationDistance Categories Subject
to Potential Contamination

Population

Value

Onsite	10.0	0.4000
> 0 to 1/4 mile	327.0	13.1000
> 1/4 to 1/2 mile	901.0	2.8000
> 1/2 to 1 mile	1987.0	2.6000
> 1 to 2 miles	1380.0	0.8000
> 2 to 3 miles	1002.0	0.4000
> 3 to 4 miles	0.0	0.0000

Potential Contaminantion Factor: 20.0000

Documentation for Population Onsite Distance Category:

There are approximately 10 people documented on-site (Ref. 6, p.8).

Reference: 6

Documentation for Population > 0 to 1/4 mile Distance Category:

There are approximately 327 people in the target distance category (Ref. 3 p.002).

Reference: 3

Documentation for Population > 1/4 to 1/2 mile Distance Category:

There are approximately 901 people in the distance category (Ref.3 p.002).

Reference: 3

Documentation for Population > 1/2 to 1 mile Distance Category:

There are approximately 1987 people in the distance category (Ref.3 p.002).

Reference: 3

Documentation for Population > 1 to 2 miles Distance Category:

There are approximately 1380 people in the distance category (Ref.3, p.002).

Reference: 3

Documentation for Population > 2 to 3 miles Distance Category:

There are approximately 1002 people in the distance category (Ref.2, p. 002).

Reference: 3

Documentation for Population > 3 to 4 miles Distance Category:

There are no known people in the distance category (Ref.3, p.002).

Reference: 3

Nearest Individual Factor

Level of Contamination: Potential

Distance in miles: 0 to 1/8

Nearest Individual Value: 20

Documentation for Nearest Individual:

The distance to the nearest residence is estimated to be 0.25 miles away (Ref. 3 p. 02).

Reference: 3

Resources

Resource Use: NO

Resource Value: 0

Documentation for Resources:

No resources identified.

Reference: 2

Actual Contamination, Sensitive Environments

Sensitive Environment	Distance (miles)	Sensitive Environment Value
-----------------------	---------------------	-----------------------------------

- N/A and/or data not specified

Actual Contamination, Wetlands

Distance Category	Wetland Acreage	Wetland Acreage Value
----------------------	--------------------	--------------------------

- N/A and/or data not specified

=====

Sensitive Environments Actual Contamination Factor: 0.000
(Sum of Sensitive Environments + Wetlands Values)

Potential Contamination, Sensitive Environments

Sensitive Environment	Distance (miles)	Sensitive Environment Value	Distance Weight	Weighted Value/10
- N/A and/or data not specified				

Potential Contamination, Wetlands

Distance Category	Wetland Acreage	Wetland Acreage Value	Distance Weight	Weighted Value/10
> 3 to 4 miles	10.0	25.0	0.0014	0.004
> 2 to 3 miles	10.0	25.0	0.0023	0.006
> 1 to 2 miles	10.0	25.0	0.0051	0.013

Total Wetland Acreage: 30.0

Sum of Wetland Weighted Acreage Values/10: 0.022

=====

Sensitive Environment Potential Contamination Factor: 0.022

Documentation for Sensitive Environment Wetlands:

An estimated 10 acres of wetlands are belived to be present in the 1 to 2 mile radius base on a review fo topographic maps (Ref.8)

Reference: 8

Documentation for Sensitive Environment Wetlands:

Ten acres are of wetlands are estimated to be present in the 2 to 3 mile radius (Ref. 8).

Reference: 8

Documentation for Sensitive Environment Wetlands:

Ten acres of wetlands are estimated to be present in the 3 to 4 mile radius (Ref.8).

Reference: 8

REFERENCES

Thomason Lumber Company - 07/22/94

1. U.S. Environmental Protection Agency, Final Rule Hazard Ranking System FR 51532-51667, December 14, 1990.
2. Guevara, Jairo, Environmental Specialist, Ecology & Environment, Inc., "Site Inspection Report", December 23, 1980, pp. 1-20.
3. U.S. Environmental Protection Agency, Geographical Exposure Modeling System (GEMS) database, compiled from U.S. Census Bureau 1990 data, accessed May 11, 1994.
4. U.S. Department of Commerce, Weather Bureau, "Rainfall Frequency Atlas of the United States".
5. U.S. Geological Survey, Oklahoma Water Resource Board, "Statistical Summaries of Streamflow Records in Oklahoma, and Parts of Arkansas, Kansas, Missouri, and Texas", Water Resources Investigation 87-4205.
6. Thomas Burger, Environmental Research Assistant, Ok Dept. of Health, "Site Inspection Report", September 26, 1980.
7. FAX: Subject: Public Water Supply for Broken Bow. From: Tim Ward, Oklahoma Department of Environmental Quality, To: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., June 15, 1994.
8. U.S. Geological Survey, 7.5-minute topographic maps of Oklahoma: Broken Bow, 1981; Shults, 1950, photorevised 1970.
9. LETTER. Subject: Laboratory Report - Thomason Lumber Company. From: William Langley, Chief Laboratory Services Section, To: William Librizzi, Surveillance & Analysis Division, February 9, 1981.
10. LETTER. Subject: Sensitive Environment in a 4-mile Radius. From: Ian Butler, Data Coordinator, OK Natural Heritage Inventory, To: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., June 1, 1994.
11. MEMORANDUM. Subject: Thomason Lumber Company. From: James Adams, Ok Water Resource Board, To: Project Files, March 7, 1985.
12. Thomas Burger, Oklahoma State Department of Health, "Identification Preliminary Assessment", September 15, 1980.
13. Kenneth Burns, Oklahoma State Department of Health, "Tentative Disposition", October 6, 1980.
14. LETTER. Subject: Administrative Order Docket No. VI-81-062. From: Diana Dutton, Director of Enforcement Division, EPA, To: Art Thompson, President, Thomason Lumber Co., April 9, 1981.

REFERENCES

Thomason Lumber Company - 07/22/94

15. Larry D. Wright, "Tentative Disposition", January 28, 1981.
16. Amy Layne, EPA, "Tentative Disposition", November 29, 1985.
17. RECORD OF COMMUNICATION: Subject: Fish Production. From: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., To: Jack Harper, Ok Department
18. U.S. Environmental Protection Agency, "Hazard Ranking System Guidance Manual", OSWER Directive 9345.1-07, November 1992, p. 314.

REFERENCE 1

U.S. Environmental Protection Agency. Final Rule Hazard Ranking System FR. 51532-51667, December 14, 1990.

Federal Register

Friday
December 14, 1990

Part II

Environmental Protection Agency

40 CFR Part 300

Hazard Ranking System; Final Rule

01-001

REFERENCE 2

Jairo Guevara, Environmental Specialist, Ecology & Environmental, Inc., "Site Inspection Report", December 23, 1980, pp. 1-20.



REGIONAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

REGION 6 SITE NUMBER (to be assigned by HQ) OK03701

GENERAL INSTRUCTIONS: Complete Sections I and III through IV of this form as completely as possible. Then use the information on this form to develop a Tentative Disposition (Section II). File this form in its entirety in the regional Hazardous Waste Log File. Be sure to include all appropriate Supplemental Reports in the file. Submit a copy of the forms to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

OKD 007 835024

A. SITE NAME THOMASON LUMBER CO. X SA VOL 1 B. STREET (or other identifier) ON HUFFMAN Rd. - half mile South of Hwy. 70.

C. CITY Broken Bow D. STATE OK E. ZIP CODE 74728 F. COUNTY NAME McCurtain

G. SITE OPERATOR INFORMATION

1. NAME Thomason Lumber Co. - Art Thomason - President 2. TELEPHONE NUMBER (405) 584-2452

3. STREET P.O. Box 804 4. CITY Broken Bow 5. STATE OK 6. ZIP CODE 74728

H. REALTY OWNER INFORMATION (if different from operator of site)

1. NAME Same 2. TELEPHONE NUMBER

3. CITY 4. STATE 5. ZIP CODE

I. SITE DESCRIPTION

See attachment A

J. TYPE OF OWNERSHIP

☐ 1. FEDERAL ☐ 2. STATE ☐ 3. COUNTY ☐ 4. MUNICIPAL ☒ 5. PRIVATE

II. TENTATIVE DISPOSITION (complete this section last)

A. ESTIMATE DATE OF TENTATIVE DISPOSITION (mo., day, & yr.) B. APPARENT SERIOUSNESS OF PROBLEM ☐ 1. HIGH ☒ 2. MEDIUM ☐ 3. LOW ☐ 4. NONE

C. PREPARER INFORMATION

1. NAME Jairo Guevara 2. TELEPHONE NUMBER (214) 742-4521 3. DATE (mo., day, & yr.) 12/23/80

III. INSPECTION INFORMATION

A. PRINCIPAL INSPECTOR INFORMATION

1. NAME Jairo Guevara 2. TITLE Chemical Engineer - FIT

3. ORGANIZATION Ecology and Environment Inc., 1509 Main St., Dallas, TX 75201 4. TELEPHONE P.O. (area code & no.) (214) 742-4521

B. INSPECTION PARTICIPANTS

1. NAME	2. ORGANIZATION	3. TELEPHONE NO.
Debbie Vaughn	Ecology and Environment, Inc.	(214) 742-4521
Gene McDonald	"	"
Barry Nash	"	"

C. SITE REPRESENTATIVES INTERVIEWED (corporate officials, workers, residents)

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
Art Thomason	President (405) 584-2452	P.O. Box 804, Broken Bow, OK 74728
Richard Thomason	Vice-President (405) 584-2452	" " "
Jerry Montgomery	Treatment Operator (405) 584-2452	" " " SUPERFUND FILE

JUN 10 1992

REORG...

02-001

REVIEWED BY (6ASASC): J. Uccardi (1/23/81)

III. INSPECTION INFORMATION (cont.)

D. GENERATOR INFORMATION (source of waste)

1. NAME	2. TELEPHONE NO.	3. ADDRESS	4. WASTE TYPE GENERATED
Thomason Lumber Co.	(405) 584-2452	P.O. Box 804, Broken Bow, OK 74728	Creosote and Pentachlorophenol Oil sludges

E. TRANSPORTER/HAULER INFORMATION

1. NAME	2. TELEPHONE NO.	3. ADDRESS	4. WASTE TYPE TRANSPORTED
N/A			

F. IF WASTE IS PROCESSED ON SITE AND ALSO SHIPPED TO OTHER SITES, IDENTIFY OFF-SITE FACILITIES USED FOR DISPOSAL.

1. NAME	2. TELEPHONE NO.	3. ADDRESS
N/A		

G. DATE OF INSPECTION (mo., day, & yr.) 12/15/80
H. TIME OF INSPECTION 3:15 pm
I. ACCESS GAINED BY: (credentials must be shown in all cases)
☒ 1. PERMISSION ☐ 2. WARRANT

J. WEATHER (describe)

Clear; 70°F; Calm

IV. SAMPLING INFORMATION

A. Mark 'X' for the types of samples taken and indicate where they have been sent e.g., regional lab, other EPA lab, contractor, etc. and estimate when the results will be available.

1. SAMPLE TYPE	2. SAMPLE TAKEN (mark 'X')	3. SAMPLE SENT TO:	4. DATE RESULTS AVAILABLE
a. GROUNDWATER			
b. SURFACE WATER			
c. WASTE	X (1)	Houston EPA Lab 6608 Hornwood Drive Houston, TX 77074	
d. AIR			
e. RUNOFF			
f. SPILL			
g. SOIL	X (1)	" " "	
h. VEGETATION			
i. OTHER (specify)			
Sediment	X (2)	" " "	

B. FIELD MEASUREMENTS TAKEN (e.g., radioactivity, explosivity, PH, etc.)

1. TYPE	2. LOCATION OF MEASUREMENTS	3. RESULTS
Radioactivity	Around Plant	Background

02-002

IV. SAMPLING INFORMATION (continued)

C. PHOTOS

1. TYPE OF PHOTOS

☒ a. GROUND ☐ b. AERIAL
2. PHOTOS IN CUSTODY OF: EPA Region VI, Dallas, TX
(See attachments)

D. SITE MAPPED?

☒ YES. SPECIFY LOCATION OF MAPS:

Site and area maps and included as attachments 1,2 and 3.

E. COORDINATES

1. LATITUDE (deg.-min.-sec.)

34° 01' 24" N

2. LONGITUDE (deg.-min.-sec.)

94° 43' 42" W

V. SITE INFORMATION

A. SITE STATUS

☒ 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.)☐ 2. INACTIVE (Those sites which no longer receive wastes.)☐ 3. OTHER (specify):
(Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)

B. IS GENERATOR ON SITE?

☐ 1. NO☒ 2. YES (specify generator's four-digit SIC Code): 2491 and 2421

C. AREA OF SITE (in acres)

23

D. ARE THERE BUILDINGS ON THE SITE?

☐ 1. NO☒ 2. YES (specify): Storage and equipment bldgs.

VI. CHARACTERIZATION OF SITE ACTIVITY

Indicate the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

'X'	A. TRANSPORTER	'X'	B. STORER	'X'	C. TREATER	'X'	D. DISPOSER
	1. RAIL	<input checked="" type="checkbox"/>	1. PILE		1. FILTRATION		1. LANDFILL
	2. SHIP	<input checked="" type="checkbox"/>	2. SURFACE IMPOUNDMENT		2. INCINERATION		2. LANDFARM
	3. BARGE		3. DRUMS		3. VOLUME REDUCTION		3. OPEN DUMP
<input checked="" type="checkbox"/>	4. TRUCK	<input checked="" type="checkbox"/>	4. TANK, ABOVE GROUND	<input checked="" type="checkbox"/>	4. RECYCLING/RECOVERY	<input checked="" type="checkbox"/>	4. SURFACE IMPOUNDMENT
	5. PIPELINE		5. TANK, BELOW GROUND		5. CHEM./PHYS./TREATMENT		5. MIDNIGHT DUMPING
	6. OTHER (specify):		6. OTHER (specify):		6. BIOLOGICAL TREATMENT		6. INCINERATION
					7. WASTE OIL REPROCESSING		7. UNDERGROUND INJECTION
					8. SOLVENT RECOVERY		8. OTHER (specify):
					9. OTHER (specify):		

E. SUPPLEMENTAL REPORTS: If the site falls within any of the categories listed below, Supplemental Reports must be completed. Indicate which Supplemental Reports you have filled out and attached to this for..

☒ 1. STORAGE ☐ 2. INCINERATION ☐ 3. LANDFILL ☒ 4. SURFACE IMPOUNDMENT ☐ 5. DEEP WELL
☐ 6. CHEM/BIO/PHYS TREATMENT ☐ 7. LANDFARM ☒ 8. OPEN DUMP ☐ 9. TRANSPORTER ☐ 10. RECYCLOR/RECLAIMER

VII. WASTE RELATED INFORMATION

A. WASTE TYPE

☒ 1. LIQUID ☐ 2. SOLID ☒ 3. SLUDGE ☐ 4. GAS

B. WASTE CHARACTERISTICS

☐ 1. CORROSIVE ☒ 2. IGNITABLE ☐ 3. RADIOACTIVE ☐ 4. HIGHLY VOLATILE
☒ 5. TOXIC ☐ 6. REACTIVE ☐ 7. INERT ☐ 8. FLAMMABLE
☐ 9. OTHER (specify):

C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below. No. Only purchase records of pentachlorophenol, creosote and oil used in the wood preserving process. In a typical year 60,000 lbs. of PCP and 10,000 gallons of creosote are used in the plant.

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE	b. OIL	c. SOLVENTS	d. CHEMICALS	e. SOLIDS	f. OTHER
AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT
UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE
<input checked="" type="checkbox"/> (1) PAINT, PIGMENTS	<input checked="" type="checkbox"/> (1) OILY WASTES	<input checked="" type="checkbox"/> (1) HALOGENATED SOLVENTS	<input checked="" type="checkbox"/> (1) ACIDS	<input checked="" type="checkbox"/> (1) FLYASH	<input checked="" type="checkbox"/> (1) LABORATORY, PHARMACEUT.
(2) METALS SLUDGES	(2) OTHER(specify):	(2) NON-HALOGENATED SOLVENTS	(2) PICKLING LIQUORS	(2) ASBESTOS	(2) HOSPITAL
(3) POTW		(3) OTHER(specify):	(3) CAUSTICS	(3) MILLING/MINE TAILINGS	(3) RADIOACTIVE
(4) ALUMINUM SLUDGE			(4) PESTICIDES	(4) FERROUS SMELTING WASTES	(4) MUNICIPAL
<input checked="" type="checkbox"/> (5) OTHER(specify): Pentachlorophenol and creosote sludges			(5) DYES/INKS	(5) NON-FERROUS SMELTING WASTES	(5) OTHER(specify):
			(6) CYANIDE	(6) OTHER(specify):	
			(7) PHENOLS		
			(8) HALOGENS		
			(9) PCB		
			(10) METALS		
			(11) OTHER(specify):		

D. LIST SUBSTANCES OF GREATEST CONCERN WHICH ARE ON THE SITE (place in descending order of hazard)

1. SUBSTANCE	2. FORM (mark 'X')			3. TOXICITY (mark 'X')				4. CAS NUMBER	5. AMOUNT	6. UNIT
	a. SOLID	b. LIQ.	c. VAPOR	a. HIGH	b. MED.	c. LOW	d. NONE			
PCP	X	X		X				87-86-5	Unknown	
Creosote	X	X			X			8001-58-9	Unknown	

VIII. HAZARD DESCRIPTION

FIELD EVALUATION HAZARD DESCRIPTION: Place an 'X' in the box to indicate that the listed hazard exists. Describe the hazard in the space provided.

- ☒ A. HUMAN HEALTH HAZARDS The major health hazards are skin exposure (dermatitis: PCP; skin carcinogen: creosote) and inhalation of vapors. Both creosote and PCP are recognized carcinogen agents. Plant employees do not wear sufficient protective equipment(gloves; mask, etc.) during wood preservation operations.

02-004

VIII. HAZARD DESCRIPTION (continued)

☐ B. NON-WORKER INJURY/EXPOSURE☒ C. WORKER INJURY/EXPOSURE See VIII-A above☐ D. CONTAMINATION OF WATER SUPPLY☐ E. CONTAMINATION OF FOOD CHAIN☒ F. CONTAMINATION OF GROUND WATER Possible due to vertical and lateral migration of PCP and creosote. Ponds used to recover and/or separate PCP and creosote are not lined.☒ G. CONTAMINATION OF SURFACE WATER Possible contamination of nearby intermittent creek which discharges into the Yanubbee Creek. This creek discharges into the Little River which is 6 miles South of the site. Low solubility of PCP and creosote in water mitigates this contamination hazard. See photos 13, 15 and 16.

02-005

III. HAZARD DESCRIPTION (continued)☐ H. DAMAGE TO FLORA/FAUNA☐ I. FISH KILL☐ J. CONTAMINATION OF AIR☒ K. NOTICEABLE ODORS PCP, creosote and oily odors were detected during inspection.☒ L. CONTAMINATION OF SOIL Soil around ponds and processing plant is highly contaminated. See photos 7,8,9 and 10.☐ M. PROPERTY DAMAGE

02-006

VIII. HAZARD DESCRIPTION (continued)

☐ N. FIRE OR EXPLOSION

☒ Q. SPILLS/LEAKING CONTAINERS/RUNOFF/STANDING LIQUID Spills from separator tank and ponds are evident. Possible run off off-site from final pond when discharge is permitted through overflow line. See photos 3,4,5,10 and 11.

☐ P. SEWER, STORM DRAIN PROBLEMS

☒ Q. EROSION PROBLEMS Erosion was observed on sloped terrain around ponds.

☒ R. INADEQUATE SECURITY Site is not fenced.

☐ S. INCOMPATIBLE WASTES

02-007

VIII. HAZARD DESCRIPTION (continued)

☐ T. MIDNIGHT DUMPING

☐ U. OTHER (specify):

IX. POPULATION DIRECTLY AFFECTED BY SITE

A. LOCATION OF POPULATION	B. APPROX. NO. OF PEOPLE AFFECTED	C. APPROX. NO. OF PEOPLE AFFECTED WITHIN UNIT AREA	D. APPROX. NO. OF BUILDINGS AFFECTED	E. DISTANCE TO SITE (specify units)
1. IN RESIDENTIAL AREAS	180	180	45	½ mile
2. IN COMMERCIAL OR INDUSTRIAL AREAS	10	10	2	½ mile
3. IN PUBLICLY TRAVELLED AREAS	300	300	0	½ mile
4. PUBLIC USE AREAS (parks, schools, etc.)	0	0	0	½ mile

X. WATER AND HYDROLOGICAL DATA

A. DEPTH TO GROUNDWATER (specify units) 50-100 ft.	B. DIRECTION OF FLOW Southeast	C. GROUNDWATER USE IN VICINITY None
D. POTENTIAL YIELD OF AQUIFER 0-50 gpm (Antlers Aquifer)	E. DISTANCE TO DRINKING WATER SUPPLY (specify units of measure) 6 miles	F. DIRECTION TO DRINKING WATER SUPPLY East
G. TYPE OF DRINKING WATER SUPPLY		
<input type="checkbox"/> 1. NON-COMMUNITY < 15 CONNECTIONS <input checked="" type="checkbox"/> 2. COMMUNITY (specify town): <u>Broken Bow</u> > 15 CONNECTIONS		
<input checked="" type="checkbox"/> 3. SURFACE WATER <input type="checkbox"/> 4. WELL		

02-008

X. WATER AND HYDROLOGICAL DATA (continued)**H. LIST ALL DRINKING WATER WELLS WITHIN A 1/4 MILE RADIUS OF SITE**

1. WELL	2. DEPTH (specify unit)	3. LOCATION (proximity to population/buildings)	4. NON-COM- MUNITY (mark 'X')	5. COMMUN- ITY (mark 'X')
None				

I. RECEIVING WATER**1. NAME**

Yanubbee Creek

☐ 2. SEWERS☒ 3. STREAMS/RIVERS☐ 4. LAKES/RESERVOIRS☐ 5. OTHER (specify):**6. SPECIFY USE AND CLASSIFICATION OF RECEIVING WATERS**

Public and private water supplies, fish and wildlife, agriculture, municipal and industrial cooling water, primary and secondary recreation, aesthetics; small mouth bass spawning grounds.

XI. SOIL AND VEGETATION DATA**LOCATION OF SITE IS IN:**☐ A. KNOWN FAULT ZONE☐ B. KARST ZONE☐ C. 100 YEAR FLOOD PLAIN☐ D. WETLAND☐ E. A REGULATED FLOODWAY☐ F. CRITICAL HABITAT☐ G. RECHARGE ZONE OR SOLE SOURCE AQUIFER**XII. TYPE OF GEOLOGICAL MATERIAL OBSERVED**

Mark 'X' to indicate the type(s) of geological material observed and specify where necessary, the component parts.

'X'	A. OVERBURDEN	'X'	B. BEDROCK (specify below)	'X'	C. OTHER (specify below)
X	1. SAND 10%	X	Paluxy Sand	X	Soil: sandy clay loam
X	2. CLAY 60%				
X	3. GRAVEL 30%				

XIII. SOIL PERMEABILITY☐ A. UNKNOWN☐ B. VERY HIGH (100,000 to 1000 cm/sec.)☐ C. HIGH (1000 to 10 cm/sec.)☒ D. MODERATE (10 to .1 cm/sec.)☐ E. LOW (.1 to .001 cm/sec.)☐ F. VERY LOW (.001 to .00001 cm/sec.)**G. RECHARGE AREA**

Adjacent creek flows Northeast towards Yanubbee Creek.

☒ 1. YES☐ 2. NO

3. COMMENTS:

H. DISCHARGE AREA☐ 1. YES☒ 2. NO

3. COMMENTS:

I. SLOPE**1. ESTIMATE % OF SLOPE**

10-20%

2. SPECIFY DIRECTION OF SLOPE, CONDITION OF SLOPE, ETC.

Slope off of the property to the North, East and South is 20% and to the West approx. 10%. The slopes have heavy vegetation with points of erosion between the ponds.

J. OTHER GEOLOGICAL DATA

The site is a small knoll with the potentiality of surface flow to go in 3 directions. Area of major concern is on the Southeastern side where the sludge ponds are located. Any overflow or run-off from them flows East-Northeast. The adjacent creek on the Southeastern side of the site is intermittent and flows North-Northeast towards a first order tributary of Yanubbee Creek. Regional hydrologic flow is towards the Southeast.

XIV. PERMIT INFORMATION

List all applicable permits held by the site and provide the related information.

A. PERMIT TYPE (e.g., RCRA, State NPDES, etc.)	B. ISSUING AGENCY	C. PERMIT NUMBER	D. DATE ISSUED (mo., day, & yr.)	E. EXPIRATION DATE (mo., day, & yr.)	F. IN COMPLIANCE (mark 'X')		
					1. YES	2. NO	3. UNKNOWN
Unpermitted							

XV. PAST REGULATORY OR ENFORCEMENT ACTIONS

☒ NONE ☐ YES (summarize in this space)

NOTE: Based on the information in Sections III through XV, fill out the Tentative Disposition (Section II) information on the first page of this form.

02-010

SURFACE IMPOUNDMENTS SITE INSPECTION REPORT
(Supplemental Report)

INSTRUCTION
Answer and Explain
as Necessary.

1. TYPE OF IMPOUNDMENT

Pond A (PCP and creosote separation)

2. STABILITY/CONDITION OF EMBANKMENTS

Some instability and erosion of embankments observed. See photo #5.

3. EVIDENCE OF SITE INSTABILITY (Erosion, Settling, Sink Holes, etc.)

☒ YES ☐ NO Erosion observed in ponds area where slope is steep.

4. EVIDENCE OF DISPOSAL OF IGNITABLE OR REACTIVE WASTE

☒ YES ☐ NO

5. ONLY COMPATIBLE WASTES ARE STORED OR DISPOSED OF IN THE IMPOUNDMENT

☒ YES ☐ NO

6. RECORDS CHECKED FOR CONTENTS AND LOCATION OF EACH SURFACE IMPOUNDMENT

☐ YES ☒ NO

7. IMPOUNDMENT HAS LINER SYSTEM

☐ YES ☒ NO

7a. INTEGRITY OF LINER SYSTEM CHECKED

☐ YES ☐ NO N/A

7b. FINDINGS

N/A

8. SOIL STRUCTURE AND SUBSTRUCTURE

Moderate Permeability

9. MONITORING WELLS

☐ YES ☒ NO

10. LENGTH, WIDTH, AND DEPTH

LENGTH 80 ft. WIDTH 80 ft. DEPTH 10 ft.

11. CALCULATED VOLUMETRIC CAPACITY

64,000 cubic feet

12. PERCENT OF CAPACITY REMAINING

15%

13. ESTIMATE FREEBOARD

1.5 ft.

14. SOLIDS DEPOSITION

☒ YES ☐ NO

15. DREDGING DISPOSAL METHOD

No dredging has been performed

16. OTHER EQUIPMENT

None

02-011

SURFACE IMPOUNDMENTS SITE INSPECTION REPORT
(Supplemental Report)

INSTRUCTION
Answer and Explain
as Necessary.

1. TYPE OF IMPOUNDMENT

Pond B (filled with sawdust to act as a filter aid).

2. STABILITY/CONDITION OF EMBANKMENTS

No embankments. See photo #10.

3. EVIDENCE OF SITE INSTABILITY (Erosion, Settling, Sink Holes, etc.)

☒ YES ☐ NO Erosion observed in pond area where slope is steep.

4. EVIDENCE OF DISPOSAL OF IGNITABLE OR PEAC/LIVE WASTE

☒ YES ☐ NO

5. ONLY COMPATIBLE WASTES ARE STORED OR DISPOSED OF IN THE IMPOUNDMENT

☐ YES ☒ NO

6. RECORDS CHECKED FOR CONTENTS AND LOCATION OF EACH SURFACE IMPOUNDMENT

☐ YES ☒ NO

7. IMPOUNDMENT HAS LINER SYSTEM

☐ YES ☒ NO

7a. INTEGRITY OF LINER SYSTEM CHECKED

☐ YES ☐ NO N/A

7b. FINDINGS

N/A

8. SOIL STRUCTURE AND SUBSTRUCTURE

Moderate Permeability

9. MONITORING WELLS

☐ YES ☒ NO

10. LENGTH, WIDTH, AND DEPTH

LENGTH 25 ft. WIDTH 25 ft. DEPTH 15 ft.

11. CALCULATED VOLUMETRIC CAPACITY

9,375 cubic feet

12. PERCENT OF CAPACITY REMAINING

0%

13. ESTIMATE FREEBOARD

None

14. SOLIDS DEPOSITION

☒ YES ☐ NO

15. DREDGING DISPOSAL METHOD

No dredging has been performed

16. OTHER EQUIPMENT

None

02-012

SURFACE IMPOUNDMENTS SITE INSPECTION REPORT
(Supplemental Report)

INSTRUCTION
Answer and Explain
as Necessary.

1. TYPE OF IMPOUNDMENT

Pond C (final pond)

2. STABILITY/CONDITION OF EMBANKMENTS

No embankments exists

3. EVIDENCE OF SITE INSTABILITY (Erosion, Settling, Sink Holes, etc.)

☒ YES ☐ NO Erosion observed in ponds area where slope is steep. See photo #14.

4. EVIDENCE OF DISPOSAL OF IGNITABLE OR REACTIVE WASTE

☒ YES ☐ NO

5. ONLY COMPATIBLE WASTES ARE STORED OR DISPOSED OF IN THE IMPOUNDMENT

☒ YES ☐ NO

6. RECORDS CHECKED FOR CONTENTS AND LOCATION OF EACH SURFACE IMPOUNDMENT

☐ YES ☒ NO

7. IMPOUNDMENT HAS LINER SYSTEM

☐ YES ☒ NO

7a. INTEGRITY OF LINER SYSTEM CHECKED

☐ YES ☐ NO N/A

7b. FINDINGS

N/A

8. SOIL STRUCTURE AND SUBSTRUCTURE

Moderate Permeability

9. MONITORING WELLS

☐ YES ☒ NO

10. LENGTH, WIDTH, AND DEPTH

LENGTH 50 ft. WIDTH 15 ft. DEPTH 10 ft.

11. CALCULATED VOLUMETRIC CAPACITY

7,500 cubic feet

12. PERCENT OF CAPACITY REMAINING

0-5%

13. ESTIMATE FREEBOARD

0-0.5 ft.

14. SOLIDS DEPOSITION

☒ YES ☐ NO

15. DREDGING DISPOSAL METHOD

No dredging has been performed

16. OTHER EQUIPMENT

None

02-013

SURFACE IMPOUNDMENTS SITE INSPECTION REPORT
(Supplemental Report)

INSTRUCTION
Answer and Explain
as Necessary.

1. TYPE OF IMPOUNDMENT

Pond D (used for rainwater only)

2. STABILITY/CONDITION OF EMBANKMENTS

No embankments

3. EVIDENCE OF SITE INSTABILITY (Erosion, Settling, Sink Holes, etc.)

☒ YES ☐ NO Erosion observed around ponds area where slope is steep.

4. EVIDENCE OF DISPOSAL OF IGNITABLE OR REACTIVE WASTE

☒ YES ☐ NO

5. ONLY COMPATIBLE WASTES ARE STORED OR DISPOSED OF IN THE IMPOUNDMENT

☒ YES ☐ NO

6. RECORDS CHECKED FOR CONTENTS AND LOCATION OF EACH SURFACE IMPOUNDMENT

☐ YES ☒ NO

7. IMPOUNDMENT HAS LINER SYSTEM

☐ YES ☒ NO

7a. INTEGRITY OF LINER SYSTEM CHECKED

☐ YES ☐ NO N/A

7b. FINDINGS

N/A

8. SOIL STRUCTURE AND SUBSTRUCTURE

Moderate Permeability

9. MONITORING WELLS

☐ YES ☒ NO

10. LENGTH, WIDTH, AND DEPTH

LENGTH 50 ft. WIDTH 25 ft. DEPTH 10 ft.

11. CALCULATED VOLUMETRIC CAPACITY

12,500 cubic feet

12. PERCENT OF CAPACITY REMAINING

3 to 4 ft.

13. ESTIMATE FREEBOARD

30 to 40%

14. SOLIDS DEPOSITION

☐ YES ☒ NO

15. DREDGING DISPOSAL METHOD

No dredging has been performed

16. OTHER EQUIPMENT

None

02-014

STORAGE FACILITIES SITE INSPECTION REPORT
(Supplemental Report)

INSTRUCTION
Answer and Explain
as Necessary.

1. STORAGE AREA HAS CONTINUOUS IMPERVIOUS BASE

☐ YES ☒ NO

2. STORAGE AREA HAS A CONFINEMENT STRUCTURE

☐ YES ☒ NO

3. EVIDENCE OF LEAKAGE/OVERFLOW (If "Yes", document where and how much runoff is overflowing or leaking from containment)

☒ YES ☐ NO Evidence of overflow was seen in separator tank. Line from separator tank to pond is broken (see photo #6).

4. ESTIMATE TYPE AND NUMBER OF BARRELS/CONTAINERS

None

5. GLASS OR PLASTIC STORAGE CONTAINERS USED

☐ YES ☒ NO

6. ESTIMATE NUMBER AND CAPACITY OF STORAGE TANKS

Five-40,000 cubic feet total capacity

7. NOTE LABELING ON CONTAINERS

N/A

8. EVIDENCE OF LEAKAGE CORROSION OR BULGING OF BARRELS/CONTAINERS/STORAGE TANKS (If "Yes", document evidence. Describe location and extent of damage. Take PHOTOGRAPHS)

☐ YES ☒ NO

9. DIRECT VENTING OF STORAGE TANKS

☐ YES ☒ NO

10. CONTAINERS HOLDING INCOMPATIBLE SUBSTANCES (If "Yes", document evidence. Describe location and identity of hazardous waste. Take PHOTOGRAPHS.)

☐ YES ☒ NO

11. INCOMPATIBLE SUBSTANCES STORED IN CLOSE PROXIMITY (If "Yes", document evidence. Describe location and identity of hazardous waste. Take PHOTOGRAPHS.)

☐ YES ☒ NO

12. ADEQUATE CONTAINER WASHING AND REUSE PRACTICES

☐ YES ☐ NO N/A

13. ADEQUATE PRACTICES FOR DISPOSAL OF EMPTY STORAGE CONTAINERS

☐ YES ☐ NO N/A

ATTACHMENT A
POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT SUPPLEMENT SHEET

Instruction - This sheet is provided to give additional information in explanation of a question on the form T2070-3.

Corresponding
number on form

Additional Remark and/or Explanation

I-1

Active pentachlorophenol and creosote wood preserving plant. Separator tank and ponds used to recover and/or separate PCP and creosote from water are located on terrain with a slope up to 20%. Final pond contents are discharged down the slope to a nearby intermittent creek. Present capacity of plant is only 40% due to the considerable decrease in sales of preserved wood products.

02-016

SAMPLING POINTS

- 1 - POND C: ~~AQUEOUS~~ HAZARDOUS SAMPLE - LIQUID
- 2 - PATH OF CONTAMINANT - SOIL SAMPLE (OFF SITE).
- 3 - ADJACENT CREEK (UPSTREAM) SEDIMENT SAMPLE.
- 4 - ADJACENT CREEK (DOWNSTREAM) SEDIMENT SAMPLE.

THOMASON LUMBER CO.

HWY 70



1086 ft.

ACCESS ROAD

SAWDUST MILL Bldgs

234 ft

1000 ft

484 ft

PCP
PCP BLEND TANK
AIR TANK
EMPTY
CREOSOTE TANK

SEPARATOR TANK

POND B FOR RAIN WATER ONLY

POND B SAWDUST PILE

#1 POND C

#4

#2

840 ft

480 ft

PROPERTY LINE

△ △ PILES OF WOOD (TREATED AND UNTREATED)


/ / / STEEP SLOPE
○ SAMPLING POINTS

ATTACHMENT 1

02-018

Site Location Map

Broken Bow, OK
December 1980



ATTACHMENT 2

02-019

Not to Scale

REFERENCE 3

U.S. Environmental Protection Agency, Geographical Exposure Modeling System (GEMS) database, compiled from U.S. Census Bureau 1990 data, accessed May 11, 1994.

THOMASON LUMBER COMPANY
GEMS SEARCH
MAY 11, 1994

COVERAGE

=====

STATE COUNTY STATE NAME

COUNTY NAME

40 89 Oklahoma

Mc Curtain Co

CENTER POINT AT STATE : 40 Oklahoma

COUNTY : 89 Mc Curtain Co

REGION OF THE COUNTRY

=====

Zipcode found: 74728 at a distance of 1.1 Km

STATE	CITY NAME	FIPSCODE	LATITUDE	LONGITUDE
-----	-----	-----	-----	-----
OK	BROKEN BOW	40089	34.0250	94.7400

03-001

CENSUS DATA

=====

Thomason Lumber Company

LATITUDE 34: 1:24 LONGITUDE 94:43:42 1990 POPULATION

	SECTOR						
KM	0-1/4	1/4-1/2	1/2-1	1-2	2-3	3-4	TOTALS
	0.00-.400	.400-.800	.800-1.60	1.60-3.20	3.20-4.80	4.80-6.40	
S 1	327	585	547	794	0	0	2253
S 2	0	0	0	0	1002	0	1002
S 3	0	0	446	0	0	0	446
S 4	0	316	994	586	0	0	1896
RING	327	901	1987	1380	1002	0	5597
TOTALS							

STAR STATION

=====

WBAN				PERIOD OF	DISTANCE
NUMBER	STATION NAME	LATITUDE	LONGITUDE	RECORD	(km)
13977	TEXARKANA/WEBB AR	33.4500	94.0000	1963-1967	92.7
13964	FT SMITH AR	35.3333	94.3667	1955-1974	149.2
13923	SHERMAN/PERRIN TX	33.7167	96.6667	1966-1976	182.0
13957	SHREVEPORT LA	32.4667	93.8167	1970-1974	192.6
13972	TYLER/POUNDS TX	32.3667	95.4000	1950-1954	194.4
93992	ELDORADO/GOODWIN AR	33.2167	92.8000	1950-1954	199.6
13960	DALLAS/LOVE TX	32.8500	96.8500	1967-1971	236.0

=====

STATE : OKLAHOMA

LATITUDE : 34: 1:24 LONGITUDE : 94:43:42

THE STATION IS INSIDE H.U. 11140107

GROUND WATER ZONE : 7

RUNOFF SOIL TYPE : 2

EROSION : 5.9760E-04 CM/MONTH

DEPTH TO GROUND WATER BETWEEN : 9.1440E+02 AND 1.8290E+04

FIELD CAPACITY FOR TOP SOIL : 7.2000E-02

EFFECTIVE POROSITY BETWEEN : 1.0000E-02 AND 1.0000E-01

SEEPAGE TO GROUNDWATER BETWEEN : 2.7800E+02 AND 2.7800E+03 CM/MONTH

DISTANCE TO DRINKING WELL : 2.7000E+04 CM

U.S. CITY

=====

STATE	PLACE NAME	FIPSCODE	LATITUDE	LONGITUDE
-------	------------	----------	----------	-----------

-----	-----	-----	-----	-----
-------	-------	-------	-------	-------

OK	BROKEN BOW	40089	34.0250	94.7400
----	------------	-------	---------	---------

03-003

REFERENCE 4

U.S. Department of Commerce, Weather Bureau, "Rainfall Frequency Atlas of the United States".

U.S. DEPARTMENT OF COMMERCE
Luther H. Thomas, Secretary

WEATHER BUREAU
D. W. Henderson, Chief

TECHNICAL PAPER NO. 40

RAINFALL FREQUENCY ATLAS OF THE UNITED STATES

for Durations from 30 Minutes to 24 Hours and
Return Periods from 1 to 100 Years


Prepared by
DAVID M. HENSEFIELD
Cooperative Studies Section, Hydrologic Services Division
for
Engineering Division, Soil Conservation Service
U.S. Department of Agriculture



Post-It™ brand fax transmittal memo 7671		# of pages ▶ 5
To	ABRAHAM LYTWYN	From JIM DENINGER
Co.	FLUOR DANIEL	Co. FLUOR DANIEL
Dept.	ESB	Phone # 214 450 4000
Fax #	214 630 4993	Fax #

100-10

2-YEAR 24-HOUR RAINFALL (INCHES)



04-002

REFERENCE 5

U.S. Geological Survey, Oklahoma Water Resource Board, "Statistical Summaries of Streamflow Records in Oklahoma, and Parts of Arkansas, Kansas, Missouri, and Texas", Water Resources Investigation No. 87-4205.

V13073

405-231-4254

Climatological 325-2541

STATISTICAL SUMMARIES OF STREAMFLOW ^(EILEN) RECORDS IN OKLAHOMA AND PARTS OF ARKANSAS, MISSOURI, AND TEXAS THROUGH 1984 _{Cooper}

By David C. Heimann and Robert L. Tortorelli

U.S. GEOLOGICAL SURVEY
Water-Resources Investigations Report 87-4205

Prepared in cooperation with the
OKLAHOMA WATER RESOURCES BOARD



Oklahoma City, Oklahoma
1988

05-001

RED RIVER BASIN

07338500 LITTLE RIVER BELOW LUKFATA CREEK NEAR IDABEL, OK

LOCATION.--Lat 33°56'28", long 94°45'30", in SE 1/4 SE 1/4 sec.14, T.7 S., R.24 E., McCurtain County, Hydrologic Unit 11140107, on left bank at downstream side of bridge on U.S. Highway 70 just downstream from Lukfata Creek, 5.0 mi northeast of Idabel, and at mile 103.4.

DRAINAGE AREA.--1,226 mi².

PERIOD OF RECORD.--October 1946 to current year.

REMARKS.--Flow regulated since June 1969 by Pine Creek Lake, 41.9 mi upstream.

STREAMFLOW REGULATED

MONTHLY AND ANNUAL MEAN DISCHARGES 1969-84

MONTH	MAXIMUM (CFS)	MINIMUM (CFS)	MEAN (CFS)	STAN- DARD DEVI- ATION (CFS)	COEFFI- CIENT OF VARI- ATION	PERCENT OF ANNUAL RUNOFF
OCTOBER	2640	26	815	973	1.2	4.1
NOVEMBER	7890	46	1720	2470	1.4	8.6
DECEMBER	10300	146	2440	2670	1.1	12.2
JANUARY	3170	157	1460	974	0.66	7.3
FEBRUARY	6550	176	2320	1660	0.71	11.6
MARCH	7730	304	3080	1940	0.63	15.4
APRIL	6190	521	2240	1560	0.70	11.2
MAY	5800	673	2910	1560	0.54	14.6
JUNE	6040	47	1910	1980	1.0	9.5
JULY	1170	31	283	314	1.1	1.4
AUGUST	676	19	162	183	1.1	0.8
SEPTEMBER	6990	25	648	1720	2.7	3.2
ANNUAL	3420	676	1660	760	0.46	100

MAGNITUDE AND PROBABILITY OF ANNUAL LOW FLOW
BASED ON PERIOD OF RECORD 1970-84

PERIOD (CON- SECUTIVE DAYS)	DISCHARGE, IN CFS, FOR INDICATED RECURRENCE INTERVAL, IN YEARS, AND NON-EXCEEDANCE PROBABILITY, IN PERCENT			
	2 50%	5 20%	10 10%	20 5%
1	21	13	9.8	7.5
3	24	16	12	9.8
7	26	17	14	11
14	29	19	15	12
30	35	23	19	16
60	57	30	22	17
90	85	40	29	23
120	144	57	36	24
183	372	164	109	79

MAGNITUDE AND PROBABILITY OF ANNUAL HIGH FLOW
BASED ON PERIOD OF RECORD 1969-84MAGNITUDE AND PROBABILITY OF INSTANTANEOUS PEAK FLOW
BASED ON 16 YEARS OF RECORD

DISCHARGE, IN CFS, FOR INDICATED RECURRENCE INTERVAL IN YEARS, AND EXCEEDANCE PROBABILITY, IN PERCENT					
2 50%	5 20%	10 10%	25 4%	50 2%	100 1%
11800	19100	29800	56300	93200	156000

STATION SKEW = 2.90

PERIOD (CON- SECUTIVE DAYS)	DISCHARGE, IN CFS, FOR INDICATED RECURRENCE INTERVAL, IN YEARS, AND EXCEEDANCE PROBABILITY, IN PERCENT					
	2 50%	5 20%	10 10%	25 4%	50 2%	100 1%
1	12000	18500	26400	42600	61600	89400
3	11000	16400	22400	33900	46400	63700
7	8260	11700	14900	20300	25600	32100
15	7150	9700	11500	13900	15700	17700
30	5690	7780	9160	10900	12200	13500
60	4120	5600	6550	7730	8590	9440
90	3390	4660	5490	6540	7310	8080

DURATION TABLE OF DAILY MEAN FLOW FOR PERIOD OF RECORD 1969-84

DISCHARGE, IN CFS, WHICH WAS EQUALED OR EXCEEDED FOR INDICATED PERCENT OF TIME																
1%	5%	10%	15%	20%	30%	40%	50%	60%	70%	80%	90%	95%	98%	99%	99.5%	99.9%
11300	7620	5640	3930	2760	1430	791	449	263	142	72	38	27	20	16	14	10

REFERENCE 6

Thomas Burger, Environmental Resource Research Assistant, Ok Department of Health,
"Site Inspection Report", September 26, 1980.

EPA

POTENTIAL HAZARDOUS WASTE SITE
ACTION REPORT

REGION 6 SITE NUMBER (to be assigned by HQ) OK03701

GENERAL INSTRUCTIONS: Complete Sections I and III through XV of this form as completely as possible. Then use the information on this form to develop a Tentative Disposition (Section II). File this form in its entirety in the regional Hazardous Waste Log File. Be sure to include all appropriate Supplemental Reports in the file. Submit a copy of the forms to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

AKD007 335 527

A. SITE NAME *Thomson Lumber Co.*
B. STREET (or other identifier)
C. CITY *Broken Bow* D. STATE *OK* E. ZIP CODE *74724* F. COUNTY NAME *McCurtain*

G. SITE OPERATOR INFORMATION

1. NAME *Art Thomson* 2. TELEPHONE NUMBER *(405) 584-2452*
3. STREET 4. CITY *Broken Bow* 5. STATE *OK* 6. ZIP CODE

H. REALTY OWNER INFORMATION (if different from operator of site)

1. NAME *NA* 2. TELEPHONE NUMBER
3. CITY 4. STATE 5. ZIP CODE

I. SITE DESCRIPTION

PCPs creosote wood treatment

J. TYPE OF OWNERSHIP

☐ 1. FEDERAL ☐ 2. STATE ☐ 3. COUNTY ☐ 4. MUNICIPAL ☒ 5. PRIVATE

II. TENTATIVE DISPOSITION (complete this section last)

A. ESTIMATE DATE OF TENTATIVE DISPOSITION (mo., day, & yr.) *10-15-80*
B. APPARENT SERIOUSNESS OF PROBLEM
☐ 1. HIGH ☒ 2. MEDIUM ☐ 3. LOW ☐ 4. NONE

C. PREPARER INFORMATION

1. NAME *Thomas S. Burch* 2. TELEPHONE NUMBER *(405) 271-5338* 3. DATE (mo., day, & yr.) *9-26-80*

III. INSPECTION INFORMATION

A. PRINCIPAL INSPECTOR INFORMATION

1. NAME *Thomas S. Burch* 2. TITLE *Environmental Research Asst.*
3. ORGANIZATION *OSDH* 4. TELEPHONE NO. (area code & no.) *(405) 271-5338*

B. INSPECTION PARTICIPANTS

1. NAME	2. ORGANIZATION	3. TELEPHONE NO.
<i>none</i>		
		<i>SUPERFUND FILE</i>
		<i>JUN 10 1992</i>

C. SITE REPRESENTATIVES INTERVIEWED (corporate officials, workers, residents)

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
<i>Art Thomson</i>	<i>Pres</i>	<i>Thomson Co.</i>
<i>Richard Thomson</i>	<i>Vice-pres.</i>	
<i>"Doc" Thomson</i>	<i>part owner</i>	
<i>Joe Roberts</i>	<i>treatment operator</i>	

06-001

REVIEWED BY



HAZARDOUS WASTE SITE INSPECTION REPORT

REGION 6 SITE NUMBER (to be assigned by HQ) OK03701

GENERAL INSTRUCTIONS: Complete Sections I and III through XV of this form as completely as possible. Then use the information on this form to develop a Tentative Disposition (Section II). File this form in its entirety in the regional Hazardous Waste Log File. Be sure to include all appropriate Supplemental Reports in the file. Submit a copy of the forms to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME <i>Thomas Lumber Co</i>		B. STREET (or other identifier)	
C. CITY <i>Broken Bow</i>	D. STATE <i>OK</i>	E. ZIP CODE <i>74728</i>	F. COUNTY NAME <i>Murtain</i>
G. SITE OPERATOR INFORMATION			
1. NAME <i>Art Thomason</i>		2. TELEPHONE NUMBER <i>(405) 584-2452</i>	
3. STREET	4. CITY <i>Broken Bow</i>	5. STATE <i>OK</i>	6. ZIP CODE
H. REALTY OWNER INFORMATION (if different from operator of site)			
1. NAME <i>NA</i>		2. TELEPHONE NUMBER	
3. CITY	4. STATE	5. ZIP CODE	

I. SITE DESCRIPTION
PCP & creosote wood treatment

J. TYPE OF OWNERSHIP

☐ 1. FEDERAL ☐ 2. STATE ☐ 3. COUNTY ☐ 4. MUNICIPAL ☒ 5. PRIVATE

II. TENTATIVE DISPOSITION (complete this section last)

A. ESTIMATE DATE OF TENTATIVE DISPOSITION (mo., day, & yr.) <i>10-15-80</i>	B. APPARENT SERIOUSNESS OF PROBLEM <input type="checkbox"/> 1. HIGH <input checked="" type="checkbox"/> 2. MEDIUM <input type="checkbox"/> 3. LOW <input type="checkbox"/> 4. NONE
--	---

C. PREPARER INFORMATION

1. NAME <i>Thomas J. Burge</i>	2. TELEPHONE NUMBER <i>(405) 271-5338</i>	3. DATE (mo., day, & yr.) <i>9-26-80</i>
-----------------------------------	--	---

III. INSPECTION INFORMATION

A. PRINCIPAL INSPECTOR INFORMATION	
1. NAME <i>Thomas J. Burge</i>	2. TITLE <i>Environmental Research Asst.</i>
3. ORGANIZATION <i>OSDH</i>	4. TELEPHONE NO. (area code & no.) <i>(405) 271-5338</i>

B. INSPECTION PARTICIPANTS

1. NAME	2. ORGANIZATION	3. TELEPHONE NO.
<i>None</i>		

C. SITE REPRESENTATIVES INTERVIEWED (corporate officials, workers, residents)

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
<i>Art Thomason</i>	<i>Pres</i>	<i>Thomas Lumber Co.</i>
<i>Richard Thomason</i>	<i>Vice-pres</i>	
<i>"Doc" Thomason</i>	<i>part owner</i>	
<i>Joe Roberts</i>	<i>treatment operator</i>	

06-002

INCOMPLETE/MISSING DOCUMENT

THE

second page

**COULD NOT BE
LOCATED
DURING THE FILE
REORGANIZATION**

IV. SAMPLING INFORMATION (continued)

C. PHOTOS

1. TYPE OF PHOTOS

☒ a. GROUND ☐ b. AERIAL

2. PHOTOS IN CUSTODY OF

OSDH

D. SITE MAPPED?

☐ YES. SPECIFY LOCATION OF MAPS

UKN

E. COORDINATES

1. LATITUDE (deg.-min.-sec.)

34° 1' 28"

2. LONGITUDE (deg.-min.-sec.)

94° 43' 27"

V. SITE INFORMATION

A. SITE STATUS

☒ 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.)

☐ 2. INACTIVE (Those sites which no longer receive wastes.)

☐ 3. OTHER(specify):
(Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)

B. IS GENERATOR ON SITE?

☐ 1. NO

☒ 2. YES(specify generator's four-digit SIC Code): 2491

C. AREA OF SITE (In acres)

19

D. ARE THERE BUILDINGS ON THE SITE?

☐ 1. NO

☒ 2. YES(specify):

Treatment shed

VI. CHARACTERIZATION OF SITE ACTIVITY

Indicate the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

X	A. TRANSPORTER	X	B. STORER	X	C. TREATER	X	D. DISPOSER
	1. RAIL		1. PILE		1. FILTRATION		1. LANDFILL
	2. SHIP		2. SURFACE IMPOUNDMENT		2. INCINERATION		2. LANDFARM
	3. BARGE		3. DRUMS		3. VOLUME REDUCTION		3. OPEN DUMP
	4. TRUCK		4. TANK, ABOVE GROUND		4. RECYCLING/RECOVERY	<input checked="" type="checkbox"/>	4. SURFACE IMPOUNDMENT
	5. PIPELINE		5. TANK, BELOW GROUND	<input checked="" type="checkbox"/>	5. CHEM./PHYS./TREATMENT		5. MIDNIGHT DUMPING
	6. OTHER(specify):		6. OTHER(specify):		6. BIOLOGICAL TREATMENT		6. INCINERATION
					7. WASTE OIL REPROCESSING		7. UNDERGROUND INJECTION
					8. SOLVENT RECOVERY		8. OTHER(specify):
					9. OTHER(specify):		

E. SUPPLEMENTAL REPORTS: If the site falls within any of the categories listed below, Supplemental Reports must be completed. Indicate which Supplemental Reports you have filled out and attached to this for..

- ☐ 1. STORAGE ☐ 2. INCINERATION ☐ 3. LANDFILL ☐ 4. SURFACE IMPOUNDMENT ☐ 5. DEEP WELL
☐ 6. CHEM/BIO/PHYS TREATMENT ☐ 7. LANDFARM ☐ 8. OPEN DUMP ☐ 9. TRANSPORTER ☐ 10. RECYCLOR/RECLAIMER

VII. WASTE RELATED INFORMATION

A. WASTE TYPE

☒ 1. LIQUID ☐ 2. SOLID ☒ 3. SLUDGE ☐ 4. GAS

B. WASTE CHARACTERISTICS

☐ 1. CORROSIVE ☐ 2. IGNITABLE ☐ 3. RADIOACTIVE ☐ 4. HIGHLY VOLATILE
☒ 5. TOXIC ☐ 6. REACTIVE ☐ 7. INERT ☐ 8. FLAMMABLE

☐ 9. OTHER(specify):

C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below.

no

06-003

WASTE RELATED INFORMATION (continued)

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE		b. OIL		c. SOLVENTS		d. CHEMICALS		e. SOLIDS		f. OTHER	
AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE
UKN		UKN									
(1) PAINT, PIGMENTS		(1) OILY WASTES		(1) HALOGENATED SOLVENTS		(1) ACIDS		(1) FLYASH		(1) LABORATORY, PHARMACEUT.	
(2) METALS SLUDGES		(2) OTHER(specify):		(2) NON-HALOGENATED SOLVENTS		(2) PICKLING LIQUORS		(2) ASBESTOS		(2) HOSPITAL	
(3) POTW				(3) OTHER(specify):		(3) CAUSTICS		(3) MILLING/MINE TAILINGS		(3) RADIOACTIVE	
(4) ALUMINUM SLUDGE						(4) PESTICIDES		(4) FERROUS SMELTING WASTES		(4) MUNICIPAL	
(5) OTHER(specify):						(5) DYES/INKS		(5) NON-FERROUS SMELTING WASTES		(5) OTHER(specify):	
						(6) CYANIDE		(6) OTHER(specify):			
						(7) PHENOLS					
						(8) HALOGENS					
						(9) PCB					
						(10) METALS					
						(11) OTHER(specify):					

PCP & creosote treatment sludge

PCP & creosote contaminated oils

D. LIST SUBSTANCES OF GREATEST CONCERN WHICH ARE ON THE SITE (place in descending order of hazard)

1. SUBSTANCE	2. FORM (mark 'X')				3. TOXICITY (mark 'X')				4. CAS NUMBER	5. AMOUNT	6. UNIT
	a. SOLID	b. LIQ.	c. VAPOR	d. HIGH	a. MED.	b. LOW	c. NONE				
PCP	X	X			X				87-86-5	UKN	
creosote		X			X				8001-58-9	UKN	

VII. HAZARD DESCRIPTION

FIELD EVALUATION HAZARD DESCRIPTION: Place an 'X' in the box to indicate that the listed hazard exists. Describe the hazard in the space provided.

☐ A. HUMAN HEALTH HAZARDS

no

06-004

VIII. HAZARD DESCRIPTION (cont.)

☐ B. NON-WORKER INJURY/EXPOSURE*no*☐ C. WORKER INJURY/EXPOSURE*no*☐ D. CONTAMINATION OF WATER SUPPLY

slight: evidence of chronic discharges and spills that would, through run off reach Little River via Yamable Creek. Distance to river (6mi) and ~~low~~ low solubility of PCP & creosote would be mitigating factors

☐ E. CONTAMINATION OF FOOD CHAIN*no*☐ F. CONTAMINATION OF GROUND WATER*OKN*☐ G. CONTAMINATION OF SURFACE WATER*See VIII D.**06-005*

VIII. HAZARD DESCRIPTION (continued)

☐ H. DAMAGE TO FLORA/FAUNA

slight : spill scars. $< \frac{1}{5}$ acre total

☐ I. FISH KILL

UKN

☐ J. CONTAMINATION OF AIR

no

☐ K. NOTICEABLE ODORS

no

☐ L. CONTAMINATION OF SOIL

slight-mod., but confined to site.

☐ M. PROPERTY DAMAGE

UKN

06-006

III. HAZARD DESCRIPTION (contn)

☐ N. FIRE OR EXPLOSION*no*☐ O. SPILLS/LEAKING CONTAINERS/RUNOFF/STANDING LIQUID

*Ex Evidence of chronic overflow of separator. Spills
ineffectively contained by earthen dam. Sample taken.*

☐ P. SEWER, STORM DRAIN PROBLEMS*no*☐ Q. EROSION PROBLEMS*no*☐ R. INADEQUATE SECURITY*area not fenced*☐ S. INCOMPATIBLE WASTES*no*

06-007

VIII. HAZARD DESCRIPTION (continued)

☐ T. MIDNIGHT DUMPING

no

☐ U. OTHER (specify):

NA

IX. POPULATION DIRECTLY AFFECTED BY SITE

A. LOCATION OF POPULATION	B. APPROX. NO. OF PEOPLE AFFECTED	C. APPROX. NO. OF PEOPLE AFFECTED WITHIN UNIT AREA	D. APPROX. NO. OF BUILDINGS AFFECTED	E. DISTANCE TO SITE (specify units)
1. IN RESIDENTIAL AREAS	none			
2. IN COMMERCIAL OR INDUSTRIAL AREAS	10	on site	2	on site
3. IN PUBLICLY TRAVELLED AREAS	NA			
4. PUBLIC USE AREAS (parks, schools, etc.)	NA			

X. WATER AND HYDROLOGICAL DATA

A. DEPTH TO GROUNDWATER (specify unit) 50-100 feet	B. DIRECTION OF FLOW west	C. GROUNDWATER USE IN VICINITY none known
D. POTENTIAL YIELD OF AQUIFE 1 0-50 GPM	E. DISTANCE TO DRINKING WATER SUPPLY (specify unit of measure) 6 mi	F. DIRECTION TO DRINKING WATER SUPPLY west
G. TYPE OF DRINKING WATER SUPPLY		
<input type="checkbox"/> 1. NON-COMMUNITY < 15 CONNECTIONS* <input checked="" type="checkbox"/> 2. COMMUNITY (specify town): Broken Bow <input type="checkbox"/> 3. SURFACE WATER <input type="checkbox"/> 4. WELL		

06-008

X. WATER AND HYDROLOGICAL DATA (continued)

H. LIST ALL DRINKING WATER WELLS WITHIN A 1/4 MILE RADIUS OF SITE

1. WELL	2. DEPTH (specify unit)	3. LOCATION (proximity to population/buildings)	4. NON-COM- MUNITY (mark 'X')	5. COMMUN- ITY (mark 'X')
<i>none known</i>				

I. RECEIVING WATER

1. NAME

Yanabee Creek☐ 2. SEWERS☒ 3. STREAMS/RIVERS☐ 4. LAKES/RESERVOIRS☐ 5. OTHER (specify):

6. SPECIFY USE AND CLASSIFICATION OF RECEIVING WATERS

*pub. + private water supply, fish + wildlife, ag, M + I cooling water,
1° + 2° rec, aesthetics, small mouth bass.*

XI. SOIL AND VEGETATION DATA

LOCATION OF SITE IS IN

☐ A. KNOWN FAULT ZONE☐ B. KARST ZONE☐ C. 100 YEAR FLOOD PLAIN☐ D. WETLAND☐ E. A REGULATED FLOODWAY☐ F. CRITICAL HABITAT☐ G. RECHARGE ZONE OR SOLE SOURCE AQUIFER

XII. TYPE OF GEOLOGICAL MATERIAL OBSERVED

Mark 'X' to indicate the type(s) of geological material observed and specify where necessary, the component parts.

'X'	A. OVERBURDEN	'X'	B. BEDROCK (specify below)	'X'	C. OTHER (specify below)
	1. SAND		<i>fine sandy loam</i>		
	2. CLAY				
	3. GRAVEL				

XIII. SOIL PERMEABILITY

☐ A. UNKNOWN☐ B. VERY HIGH (100,000 to 1000 cm/sec.)☐ C. HIGH (1000 to 10 cm/sec.)☐ D. MODERATE (10 to .1 cm/sec.)☐ E. LOW (.1 to .001 cm/sec.)☐ F. VERY LOW (.001 to .00001 cm/sec.)

G. RECHARGE AREA

☐ 1. YES☐ 2. NO

3. COMMENTS:

H. DISCHARGE AREA

☐ 1. YES☐ 2. NO

3. COMMENTS:

I. SLOPE

1. ESTIMATE % OF SLOPE

5-30%

2. SPECIFY DIRECTION OF SLOPE, CONDITION OF SLOPE, ETC.

west - good condition

J. OTHER GEOLOGICAL DATA

06-099

XIV. PERMIT INFORMATION

List all applicable permits held by the site and provide the related information.

A. PERMIT TYPE (e.g., RCRA, State, NPDES, etc.)	B. ISSUING AGENCY	C. PERMIT NUMBER	D. DATE ISSUED (mo., day, & yr.)	E. EXPIRATION DATE (mo., day, & yr.)	F. IN COMPLIANCE (mark 'X')		
					1. YES	2. NO	3. UN- KNOWN
UKN							

XV. PAST REGULATORY OR ENFORCEMENT ACTIONS

☐ NONE ☐ YES (summarize in this space)

UKN

NOTE: Based on the information in Sections III through XV, fill out the Tentative Disposition (Section II) information on the first page of this form.

06-010

REFERENCE 7

FAX: Subject: Public Water Supply for Broken Bow. From: Tim Ward, Oklahoma Department of Environmental Quality, To: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., June 15, 1994.

MARK S. COLEMAN
Executive Director



DAVID WALTERS
Governor

State of Oklahoma
DEPARTMENT OF ENVIRONMENTAL QUALITY

FAX TRANSMITTAL SHEET

DATE:

6/15/94

TO:

ARIADNE LYTWIN

FAX #:

312-630-4993

AGENCY/CO:

MAIL CODE/
DEPARTMENT:
PHONE #:

FROM:

TIM WARD

FAX #:

(405) 271-7339

AGENCY:

OKLAHOMA DEPARTMENT OF ENVIRONMENTAL
QUALITY

SERVICE/
DIVISION:
PHONE #:

WQD

1 # OF PAGES (INCLUDING THIS SHEET)

PWSID SYSTEM
1010214 BROKEN BOW

SOURCEID SOURCE entrynum AQUIFER
01 MT FORK RIVER 1 0102

DEPTH LOCATION

806T06SR26E1M A C

Surface water intake 8.0 miles NE
of the site

PWSID SYSTEM
1021220 STILLWATER

SOURCEID SOURCE entrynum AQUIFER
01 KAW RESERVOIR 1 0212


DEPTH LOCATION

S36T26NR03E1M A C

07-001

REFERENCE 8

U.S. Geological Survey, 7.5-Minute Topographic Maps of Oklahoma: Broken Bow, 1981;
Shults, 1950, photorevised 1970.



Maped, edited, and published by the Geological Survey
Control by USGS and USC&GS
Culture and drainage in part compiled from
aerial photographs taken 1949
Topography by plane-table methods 1949-1950
Polyconic projection 1927 North American datum
10,000-foot grid based on Oklahoma coordinate system,
south zone
1000-metre Universal Transverse Mercator grid ticks,
zone 15, shown in blue

UTM GRID AND 1975 MAGNETIC NORTH
DECLINATION AT CENTER OF SHEET

SCALE 1:24,000
1 000 0 1000 2000 3000 4000 5000 6000 7000 FEET
1 0 1 2 3 4 5 6 7 8 9 10 KILOMETERS
CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929


ROAD CLASSIFICATION
Heavy duty ——— Light duty ———
Medium duty ——— Unimproved dirt ———
U. S. Route State Route

THIS MAP COMPLETES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U. S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
AND BY THE OKLAHOMA GEOLOGICAL SURVEY, NORMAN, OKLAHOMA 73069
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

SHULTS, OKLA.
N 3352.5 W 9437.5
1950

08-002

AMS 7051 I NW - SERIES V883



Approx. Location
Surface
Water Intake

Mapped, edited, and published by the Geological Survey
in cooperation with the Oklahoma Highway Department,
Oklahoma Water Resources Board, and Oklahoma State Soil
Conservation Board

Control by USGS and NOS/NOAA

Topography by photogrammetric methods from aerial photographs
taken 1977. Field checked 1978. Map edited 1981

Projection and 10,000-foot grid ticks: Oklahoma coordinate
system, south zone (Lambert conformal conic)

1000-meter Universal Transverse Mercator grid, zone 15

1927 North American Datum

To place on the predicted North American Datum 1983


move the projection lines 7 meters south and

20 meters east as shown by dashed corner ticks

There may be private inholdings within the boundaries of
the National or State reservations shown on this map


Red tint indicates area in which only landmark buildings are shown

SCALE 1:24 000



CONTOUR INTERVAL 10 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY, DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
AND BY THE OKLAHOMA GEOLOGICAL SURVEY, NORMAN, OKLAHOMA 73069
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST



ROAD CLASSIFICATION		
Primary highway, hard surface	Light duty road, hard or improved surface	
Secondary highway, hard surface	Unimproved road	
Interstate Route	U. S. Route	State Route

BROKEN BOW, OKLA.
SW 1/4 BROKEN BOW 15' QUADRANGLE
N3400-W9437.5/7.5

1981

DMA 7052 II SW-SERIES V883

08-001

REFERENCE 9

LETTER. Subject: Laboratory Report - Thomason Lumber Company. From: William Langley, Chief Laboratory Services Section, EPA, To: William Librizzi, Surveillance & Analysis Division, February 9, 1981.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
300 DOD DRIVE HOUSTON, TEXAS

DATE: February 9, 1981

SUBJECT: Laboratory Report: Thomason Lumber Company, OK 03701

FROM: William D. Langley, Chief
Laboratory Services Section, 6ASAH

TO: William J. Librizzi, Director
Surveillance and Analysis Division, 6ASA

Thru: Malcolm F. Kallus, Chief, Houston Branch, 6ASAH *Mal*

One 8-ounce water sample and three soil/sediment samples collected at or near the subject site by FIT personnel on December 15, 1980, were received at the Houston Branch Laboratory on December 19, 1981. We were requested to perform base/neutral and acid extractions of the samples, to analyze the acid extract for pentachlorophenol, to retain the base/neutral extract for possible analysis at a later date, and to retain the original sample for possible analysis for dioxin at a later date. We have complied with these requests; and additionally, we have performed a total phenols by 4-aminoantipyrine analysis as a possible, although not absolute, indicator of creosote. It should be noted that pentachlorophenol does not respond to the total phenols by 4AAP analysis.

The results of our analyses are presented below. Also attached to this report is a copy Chain of Custody Record No. 6-0154 which accompanied these samples.

1. HNB Laboratory No. 3619; Tag No. 6-1147

Source: Thomason Lumber Company; OK 03701
Station 1; Final Pond #C
8.ounce water sample.

Time Collected: 1615 hours.

Date Collected: 12/15/80.

<u>Parameter Analyzed</u>	<u>Concentration Found</u>
Pentachlorophenol	50 ug/l (ppb)
Total Phenols by 4AAP	1,715 "

SUPERFUND FILE

JUN 10 1992

REORGANIZED

2. HNB Laboratory Number 3620; Tag No. 6-1144

Source: Thomason Lumber Company; OK 03701
Station 2; 185 feet east of Pond #C
Soil.

Time Collected: 1545 hours.

Date Collected: 12/15/80.

REFERENCE 10

LETTER. Subject: Sensitive Environment in a 4-mile Radius. From: Ian Butler, Data Coordinator, Oklahoma Natural Heritage Inventory, To: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., June 1, 1994.



Oklahoma
Natural Heritage Inventory

OKLAHOMA BIOLOGICAL SURVEY
111 E. Chesapeake Street
Norman, Oklahoma 73019-0575 USA
405/325-1985
FAX 405/325-7702

Ariadne Lytwyn
Fluor Daniel
200 West Monroe Street
Chicago, IL 60606

June 1, 1994

Dear Ariadne Lytwyn,

This letter is in response to your request for information on possible endangered species or other elements of biological significance at the following sites:


- (1) Latitude 34 01 24 N and Longitude 94 43 42 W in McCurtain County, Oklahoma
- (2) Latitude 34 24 22 N and Longitude 95 26 59 W in Pushmataha County, Oklahoma
- (3) Latitude 36 09 37 N and Longitude 97 04 52 W in Payne County, Oklahoma

The Oklahoma Natural Heritage Inventory maintains a database on the status and location of rare species and significant ecological communities in Oklahoma. We have reviewed the information currently in the Heritage Inventory database and found no records of on site-elements. However, elements were found within a four mile radius from the sites. These are listed on the attached table

The Heritage Inventory database is the most current comprehensive one available on the rare biota of Oklahoma. However, such a database is only as complete as the information that has been collected. For this reason, we cannot state for certain whether or not a given site harbors rare species or significant communities. We suggest you also contact the Environmental Division of the Oklahoma Department of Wildlife Conservation, as they may have site specific information of which we are unaware.

Thank you for the opportunity to respond to your request.

Sincerely,

for 
Ian H. Butler
Data Coordinator

IHB sdl

10-001

OKLAHOMA NATURAL HERITAGE INVENTORY
TABLE OF PROXIMAL ELEMENT OCCURRENCES

REQUESTED BY: Fluor Daniel
DATE OF REQUEST: June 1, 1994

SITE SPECIES NAME	STATUS FED STATE		ONHI RANK GLOBAL STATE		LAST SEEN
SITE NAME: Latitude 34 01 24 N, Longitude 95 26 59 W					
<u>Streptanthus squamiformis</u> (A Jewelflower: forb) *	C2	none	G3	S1	1930
<u>Draba aprica</u> * (Open-Ground Whitlow-Grass: forb)	3C	none	G3	S1	1978
<u>Aristolochia reticulata</u> * (Texas Dutchman's-Pipe: forb)	none	none	G4	S2	1978
<u>Notropis atrocaudalis</u> * (Blackspot Shiner: fish)	none	none	G4	S1	1985
<u>Notropis ortenburgeri</u> * (Kiamichi Shiner: fish)	none	none	G3	S3	1955
<u>Villosa iris</u> * (Rainbow: mussel)	none	none	G4	S1	1983
<u>Villosa lienosa</u> * (Little Spectacle Case: mussel)	none	none	G3	S2	1948

SITE SPECIES NAME	STATUS FED STATE		ONHI RANK GLOBAL STATE		LAST SEEN
SITE NAME: Latitude 34 24 22 N, Longitude 95 26 59 W					
<u>Notropis ortenburgeri</u> * (Kiamichi Shiner: fish)	none	none	G3	S3	1973
<u>Clematis drummondii</u> * (Drummond Leather-Flower: forb)	none	none	G5	S1S2	1973

Elements occur on-site unless otherwise noted as follows:

* Occurrence within approximate 4 mile radius of site.

10-002

SITE SPECIES NAME	STATUS FED STATE	ONHI RANK GLOBAL STATE	LAST SEEN
----------------------	---------------------	---------------------------	-----------

SITE NAME: Latitude 36 09 37 N, Longitude 97 04 52 W

<u>Penstemon oklahomensis</u> *	none none	G3 S3	1977
(Oklahoma Beardtongue: forb)			

<u>Ulmus americana- Celti spp.</u>	none none	G2G3 S2S3	1977
(Central Bottomland Forest: bottomland community)			

Elements occur on-site unless otherwise noted as follows:

 * Occurrence within approximate 4 mile radius of site.

10-003

OKLAHOMA NATURAL HERITAGE INVENTORY
EXPLANATION OF NATURAL HERITAGE RARITY RANKINGS

Each species and natural community is given two ranks, a global (G) rank reflecting its rarity throughout the world, and, a state (S) rank reflecting its rarity within Oklahoma.

Global Rank

- G1** Critically imperiled globally because of extreme rarity (5 or fewer occurrences or very few remaining individuals or acres) or because of some factor of its biology making it especially vulnerable to extinction.
- G2** Imperiled globally because of rarity (6 to 20 occurrences or few remaining individuals or acres) or because of other factors demonstrably making it very vulnerable to extinction throughout its range.
- G3** Either very rare and local throughout its range, or found locally (even abundantly at some of its locations) in a restricted range, or because of other factors making it vulnerable to extinction throughout its range; in the range of 21 to 100 occurrences.
- G4** Apparently secure globally, though it may be quite rare in parts of its range, especially at the periphery.
- G5** Demonstrably secure globally, though it may be quite rare in parts of its range, especially at the periphery.
- GH** Historically known, with the expectation that it may be rediscovered.
- GX** Believed to be extinct.
- GU** Not yet ranked.

State Rank

- S1** Critically imperiled in Oklahoma because of extreme rarity (5 or fewer occurrences or very few remaining individuals or acres) or because of some factor of its biology making it especially vulnerable to extinction.
- S2** Imperiled in Oklahoma because of rarity (6 to 20 occurrences or few remaining individuals or acres) or because of other factors demonstrably making it very vulnerable to extinction throughout its range.
- S3** Rare and local in Oklahoma(though it may be abundant at some of its locations); in the range of 21 to 100 occurrences.
- S4** Apparently secure in Oklahoma.
- S5** Demonstrably secure in Oklahoma.
- SH** Historically known from Oklahoma, but possibly extirpated; not seen in the last 15 years.
- SR** Reported in Oklahoma, but not documented.
- SRF** Falsely reported in Oklahoma.
- S#M*** Migratory.
- S#N** Nonbreeding in Oklahoma.
- S#B** Breeding in Oklahoma
- SU** Not yet ranked.
- SX** Believed to be extirpated from Oklahoma.

* Rank number (#) included to indicate status.

Other Rank Symbols

- ?** There is a question about the given rank.
- Q** There are taxonomic questions concerning a species.
- T** Associated with global rank, indicating a global rarity rank for a particular subspecific taxon.

10-004

EXPLANATION OF STATE AND FEDERAL STATUS ABBREVIATIONS

State (Status determined by the Oklahoma Department of Wildlife Conservation)

- E** Endangered in Oklahoma.
- T** Threatened in Oklahoma.
- SN** State nominated for listing as threatened or endangered.
- SS** Species of Special Concern
 - SS1** - a species that current evidence indicates is especially vulnerable to extirpation because of limited range, low population or other factors.
 - SS2** - species identified by technical experts as possibly threatened or vulnerable to extirpation but for which additional information is needed.
- P** Statewide closed season.

Federal (Status determined by the US Fish and Wildlife Service, Office of Endangered Species)

- LE** Listed Endangered.
- PE** Proposed for listing as Endangered.
- LT** Listed Threatened.
- PT** Proposed for listing as Threatened.
- LELT** Listed Endangered in some USFWS regions and Threatened in others.
- C1** Category 1 species for listing. Species determined to be in need of protection by listing as Endangered or Threatened.
- C2** Category 2 species for listing. Species needs additional study to determine whether it should be listed as Endangered or Threatened.
- C2*** Category 2 species recommended for elevation to C1 status.
- 3C** Category 3 species. Currently, the species is not recommended for listing as Endangered or Threatened.

Additional information about the federal or state status of species may be available directly from, respectively, the US Fish and Wildlife Service, Ecological Services Office, Tulsa, (918) 581-7458, or, from the Oklahoma Department of Wildlife Conservation, Natural Resources Section, Oklahoma City, (405) 521-4616.

REFERENCE 11

MEMORANDUM. Subject: Thomason Lumber Company. From: James Adams, Oklahoma Water Resource Board, To: Project Files, March 7, 1985.

Oklahoma Water Resources Board

Date: March 7, 1985
1330 hrs.

Memo to the files

From: James C. Adams *JCA*

Subject: Thomason Lumber -- Compliance Activity

OKD 007 335 54

Remarks:

Tim Smith and I stopped and visited with Earl Hayes, the new owner of Thomason Lumber. We discussed the consent agreement at length and he agreed to sign it and respond in writing as to the items in the agreement. We then inspected the facility and discussed the plans to recover the lagoon.

The dike around the treating site was satisfactory. His plan to remove the lagoons, wastewater, contaminated soil, and contaminated sawdust was satisfactory.

I inspected the lagoon around the product catch basin and evaportaion tanks and was concerned about the lagoon walls structural stability and permeability. I told Mr. Hayes to have his Engineer evaluate these. The lagoon showed signs of slumping and I questioned if the clay would prevent the product from escaping the lagoon walls.

Mr. Hayes said he would write Mr. Jarman, returning the signed consent agreement and discuss the issues requested in the agreement.

SUPERFUND FILE

JUN 10 1992

REORGANIZ...

11-001

REFERENCE 12

Thomas Burger, Oklahoma State Department of Health, "Identification and Preliminary Assessment", September 15, 1980.

IDENTIFICATION AND PRELIMINARY ASSESSMENT

6 OK03701

NO. 5. This form is completed for use
submitted on this form is based on av
on-site inspections.

Initial hazardous waste site to help set
records and may be updated on subseq

is for site inspection. The information
forms as a result of additional inquiries

REVIEWED BY: L.D. Wright 11-21-80

GENERAL INSTRUCTIONS: Complete Sections I and III through X as completely as possible before Section II (Preliminary Assessment). File this form in the Regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

OKD 007 836324

A. SITE NAME

Thomason Lumber Co.

B. STREET (or other identifier)

C. CITY

Broken Bow

D. STATE

OK

E. ZIP CODE

74728

F. COUNTY NAME

M. Curtain

G. OWNER/OPERATOR (if known)

1. NAME

Art Thomason

2. TELEPHONE NUMBER

(405) 584-2452

H. TYPE OF OWNERSHIP

☐ 1. FEDERAL ☐ 2. STATE ☐ 3. COUNTY ☐ 4. MUNICIPAL ☒ 5. PRIVATE ☐ 6. UNKNOWN

I. SITE DESCRIPTION

PCP & creosote wood treatment

J. HOW IDENTIFIED (i.e., citizen's complaints, OSHA citations, etc.)

I.W.S.

K. DATE IDENTIFIED

(mo., day, & yr.)

9-15-80

L. PRINCIPAL STATE CONTACT

1. NAME

Don Hensch

2. TELEPHONE NUMBER

(405) 271-5338

II. PRELIMINARY ASSESSMENT (complete this section last)

A. APPARENT SERIOUSNESS OF PROBLEM.

☐ 1. HIGH ☒ 2. MEDIUM ☐ 3. LOW ☐ 4. NONE ☒ 5. UNKNOWN

B. RECOMMENDATION

☐ 1. NO ACTION NEEDED (no hazard)☐ 3. SITE INSPECTION NEEDED

a. TENTATIVELY SCHEDULED FOR:

b. WILL BE PERFORMED BY:

☒ 2. IMMEDIATE SITE INSPECTION NEEDED

a. TENTATIVELY SCHEDULED FOR:

9-17-80

b. WILL BE PERFORMED BY:

Burger

☐ 4. SITE INSPECTION NEEDED (low priority)

C. PREPARER INFORMATION

1. NAME

Thomas S. Burger

2. TELEPHONE NUMBER

(405) 271-5338

3. DATE (mo., day, & yr.)

9-15-80

III. SITE INFORMATION

A. SITE STATUS

☒ 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if in-quantity.)☐ 2. INACTIVE (Those sites which no longer receive wastes.)☐ 3. OTHER (specify):

(These sites that include such incidents as SUPERFUND sites where no regular or continuing use of the site for waste disposal has occurred.)

JUN 10 1992

B. IS GENERATOR ON SITE?

☐ 1. NO☒ 2. YES (specify generator's four-digit SIC Code): 2491 REORGANIZ...

C. AREA OF SITE (in acres)

19

D. IF APPARENT SERIOUSNESS OF SITE IS HIGH, SPECIFY COORDINATES

1. LATITUDE (deg.-min.-sec.)

2. LONGITUDE (deg.-min.-sec.)

E. ARE THERE BUILDINGS ON THE SITE?

☐ 1. NO☒ 2. YES (specify):

treatment shed

12-001

10/6

A. TRANSPORTER		B. STORER		C. TREATER		D. DISPOSER	
<input checked="" type="checkbox"/> 1. RAIL	<input checked="" type="checkbox"/> 1. PILE	<input checked="" type="checkbox"/> 1. FILTRATION	<input checked="" type="checkbox"/> 1. LANDFILL				
<input checked="" type="checkbox"/> 2. SHIP	<input checked="" type="checkbox"/> 2. SURFACE IMPOUNDMENT	<input checked="" type="checkbox"/> 2. INCINERATION	<input checked="" type="checkbox"/> 2. LANDFARM				
<input checked="" type="checkbox"/> 3. BARGE	<input checked="" type="checkbox"/> 3. DRUMS	<input checked="" type="checkbox"/> 3. VOLUME REDUCTION	<input checked="" type="checkbox"/> 3. OPEN DUMP				
<input checked="" type="checkbox"/> 4. TRUCK	<input checked="" type="checkbox"/> 4. TANK, ABOVE GROUND	<input checked="" type="checkbox"/> 4. RECYCLING/RECOVERY	<input checked="" type="checkbox"/> 4. SURFACE IMPOUNDMENT				
<input checked="" type="checkbox"/> 5. PIPELINE	<input checked="" type="checkbox"/> 5. TANK, BELOW GROUND	<input checked="" type="checkbox"/> 5. CHEM./PHYS. TREATMENT	<input checked="" type="checkbox"/> 5. MIGHT DUMPING				
<input checked="" type="checkbox"/> 6. OTHER (specify):	<input checked="" type="checkbox"/> 6. OTHER (specify):	<input checked="" type="checkbox"/> 6. BIOLOGICAL TREATMENT	<input checked="" type="checkbox"/> 6. INCINERATION				
		<input checked="" type="checkbox"/> 7. WASTE OIL REPROCESSING	<input checked="" type="checkbox"/> 7. UNDERGROUND INJECT				
		<input checked="" type="checkbox"/> 8. SOLVENT RECOVERY	<input checked="" type="checkbox"/> 8. OTHER (specify):				
		<input checked="" type="checkbox"/> 9. OTHER (specify):					

E. SPECIFY DETAILS OF SITE ACTIVITIES AS NEEDED

NA

V. WASTE RELATED INFORMATION

A. WASTE TYPE

☐ 1. UNKNOWN ☒ 2. LIQUID ☒ 3. SOLID ☐ 4. SLUDGE ☐ 5. GAS

B. WASTE CHARACTERISTICS

☐ 1. UNKNOWN ☐ 2. CORROSIVE ☐ 3. IGNITABLE ☐ 4. RADIOACTIVE ☐ 5. HIGHLY VOLATILE
☒ 6. TOXIC ☐ 7. REACTIVE ☐ 8. INERT ☐ 9. FLAMMABLE

☐ 10. OTHER (specify):

C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc., below.

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which wastes are present.

a. SLUDGE	b. OIL	c. SOLVENTS	d. CHEMICALS	e. SOLIDS	f. OTHER
AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT	AMOUNT
UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE	UNIT OF MEASURE
<input checked="" type="checkbox"/> (1) PAINT, PIGMENTS	<input checked="" type="checkbox"/> (1) OILY WASTES	<input checked="" type="checkbox"/> (1) HALOGENATED SOLVENTS	<input checked="" type="checkbox"/> (1) ACIDS	<input checked="" type="checkbox"/> (1) FLYASH	<input checked="" type="checkbox"/> (1) LABORATORY PHARMACEUTICALS
(2) METALS SLUDGES	(2) OTHER (specify):	(2) NON-HALOGENATED SOLVENTS	(2) PICKLING LIQUORS	(2) ASBESTOS	(2) HOSPITAL WASTES
(3) POTW		(3) OTHER (specify):	(3) CAUSTICS	(3) MILLING/MINE TAILINGS	(3) RADIOACTIVE WASTES
(4) ALUMINUM SLUDGE			(4) PESTICIDES	(4) FERROUS SMELTING WASTES	(4) MUNICIPAL WASTES
<input checked="" type="checkbox"/> (5) OTHER (specify):			(5) DYES/INKS	(5) NON-FERROUS SMELTING WASTES	(5) OTHER (specify):
			(6) CYANIDE	(6) OTHER (specify):	
			(7) PHENOLS		
			(8) HALOGENS		
			(9) PCB		
			(10) METALS		
			(11) OTHER (specify):		

PCP & creosote sludge

PCP & creosote contaminated oils

12-002

3. LIST SUBSTANCES OF GREATEST CONCERN

4. WASTE RELATED INFORMATION (continued)

WHICH MAY BE ON THE SITE (place in d

g order of hazard).

PCP
creosote

4. ADDITIONAL COMMENTS OR NARRATIVE DESCRIPTION OF SITUATION KNOWN OR REPORTED TO EXIST AT THE SITE.

NA

VI. HAZARD DESCRIPTION

A. TYPE OF HAZARD	B. POTENTIAL HAZARD (mark "X")	C. ALLEGED INCIDENT (mark "X")	D. DATE OF INCIDENT (mo., day, yr.)	E. REMARKS
1. NO HAZARD				
2. HUMAN HEALTH				
3. NON-WORKER INJURY/EXPOSURE				
4. WORKER INJURY				
5. CONTAMINATION OF WATER SUPPLY				
6. CONTAMINATION OF FOOD CHAIN				
7. CONTAMINATION OF GROUND WATER				
8. CONTAMINATION OF SURFACE WATER				
9. DAMAGE TO FLORA/FAUNA				
10. FISH KILL				
11. CONTAMINATION OF AIR				
12. NOTICEABLE ODORS				
13. CONTAMINATION OF SOIL				
14. PROPERTY DAMAGE				
15. FIRE OR EXPLOSION				
16. SPILLS/LEAKING CONTAINERS/ RUNOFF/STANDING LIQUIDS				
17. SEWER, STORM DRAIN PROBLEMS				
18. EROSION PROBLEMS				
19. INADEQUATE SECURITY				
20. INCOMPATIBLE WASTES				
21. MIDNIGHT DUMPING				
22. OTHER (specify):				

12-003

VII. PERMIT INFORMATION

A. INDICATE ALL APPLICABLE PERMITS HELD BY THE SITE.

- ☐ 1. NPDES PERMIT ☐ 2. SPCC PLAN ☐ 3. STATE PERMIT (specify): UKN
☐ 4. AIR PERMITS ☐ 5. LOCAL PERMIT ☐ 6. RCRA TRANSPORTER
☐ 7. RCRA STORER ☐ 8. RCRA TREATER ☐ 9. RCRA DISPOSER
☐ 10. OTHER (specify): _____

B. IN COMPLIANCE?

- ☐ 1. YES ☐ 2. NO ☒ 3. UNKNOWN

4. WITH RESPECT TO (list regulation name & number): _____

VIII. PAST REGULATORY ACTIONS

- ☐ A. NONE ☐ B. YES (summarize below)
- UKN

IX. INSPECTION ACTIVITY (past or on-going)

- ☐ A. NONE ☐ B. YES (complete items 1, 2, 3, & 4 below) UKN

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION

X. REMEDIAL ACTIVITY (past or on-going)

- ☐ A. NONE ☐ B. YES (complete items 1, 2, 3, & 4 below) UKN

1. TYPE OF ACTIVITY	2. DATE OF PAST ACTION (mo., day, & yr.)	3. PERFORMED BY: (EPA/State)	4. DESCRIPTION

NOTE: Based on the information in Sections III through X, fill out the Preliminary Assessment (Section II) information on the first page of this form.

12-004

REFERENCE 13

Kenneth Burns, Oklahoma State Department of Health, "Tentative Disposition", October 6, 1980.

Environmental Protection Agency; Site Track
n, DC 20460.

A. SITE NAME

B. STREET

OKD007 335524/

C. CITY

D. STATE

BROKEN BOW

OK

F. ZIP CODE

74728

II. TENTATIVE DISCUSSION

Indicate the recommended action(s) and agency(ies) that should be involved by marking "X" in the appropriate boxes.

RECOMMENDATION	ACTION AGENCY				
	MARK 'X'	EPA	STATE	LOCAL	PRIVATE
A. NO ACTION NEEDED - NO HAZARD					
B. INVESTIGATIVE ACTION(S) NEEDED (If yes, complete Section III.)	X		X		
C. REMEDIAL ACTION NEEDED (If yes, complete Section IV.)					
D. ENFORCEMENT ACTION NEEDED (If yes, specify in Part E whether the case will be primarily managed by the EPA or the State and what type of enforcement action is anticipated.)					

E. RATIONALE FOR DISPOSITION

Investigative Action Needed - Further ~~define~~ DEFINE PROBLEM.

F. INDICATE THE ESTIMATED DATE OF FINAL DISPOSITION
(mo., day, & yr.)

G. IF A CASE DEVELOPMENT PLAN IS NECESSARY, INDICATE THE ESTIMATED DATE ON WHICH THE PLAN WILL BE DEVELOPED (mo., day, & yr.)

H. PREPARER INFORMATION

1. NAME

KENNETH C. BURNS

2. TELEPHONE NUMBER

2. TELEPHONE NUMBER
 (405) 271-5338

3. DATE (mo., day, & yr.):

10/6/80

III. INVESTIGATIVE ACTIVITY NEEDED

A. IDENTIFY ADDITIONAL INFORMATION NEEDED TO ACHIEVE A FINAL DISPOSITION.

SUPERFUND FILE

JUN 10 1992

D. PROPOSED INVESTIGATIVE ACTIVITY (Detailed Information)

1. METHOD FOR OBTAINING NEEDED ADDITIONAL INFO.	2. SCHEDULED DATE OF ACTION (mo, day, & yr)	3. TO BE PERFORMED BY (EPA, Con- tractor, State, etc.)	4. ESTIMATED MANHOURS	5. REMARKS
a. TYPE OF SITE INSPECTION				
(1)				
(2)				
(3)				
b. TYPE OF MONITORING				
(1)				
(2)				
c. TYPE OF SAMPLING				
(1)				
(2)				

III. INVESTIGATIVE		Y NEEDED and PART B-PROPOSED		IGATIVE ACTIVITY (Continued)	
4. TYPE OF LAB ANALYSIS					
(1)					
(2)					
e. OTHER (specify)					
(1)					
(2)					
C. ELABORATE ON ANY OF THE INFORMATION PROVIDED IN PART B (on front & above) AS NEEDED TO IDENTIFY ADDITIONAL INVESTIGATIVE WORK.					

D. ESTIMATED MANHOURS BY ACTION AGENCY			
1. ACTION AGENCY	2. TOTAL ESTIMATED MANHOURS FOR INVESTIGATIVE ACTIVITIES	1. ACTION AGENCY	2. TOTAL ESTIMATED MANHOURS FOR INVESTIGATIVE ACTIVITIES
a. EPA		b. STATE	
c. EPA CONTRACTOR		d. OTHER (specify)	

IV. REMEDIAL ACTIONS

A. SHORT TERM/EMERGENCY STRATEGY (On Site & Off-Site): List all emergency actions needed to bring site under immediate control, e.g., restrict access, provide alternate water supply, etc. See instructions for a list of Key Words for each of the actions to be used in the space below.

1. ACTION	2. EST. START DATE (mo, day, & yr)	3. EST. END DATE (mo, day, & yr)	4. ACTION AGENCY (EPA, State, Private Party)	5. ESTIMATED COST	6. SPECIFY 311 OR OTHER ACTION; INDICATE THE MAGNITUDE OF THE WORK REQUIRED
				\$	
				\$	
				\$	
				\$	
				\$	
				\$	

B. LONG TERM STRATEGY (On Site & Off-Site): List all long term solutions, e.g., excavation, removal, ground water monitoring wells, etc. See instructions for a list of Key Words for each of the actions to be used in the spaces below.

1. ACTION	2. EST. START DATE (mo, day, & yr)	3. EST. END DATE (mo, day, & yr)	4. ACTION AGENCY (EPA, State, Private Party)	5. ESTIMATED COST	6. SPECIFY 311 OR OTHER ACTION; INDICATE THE MAGNITUDE OF THE WORK REQUIRED
				\$	
				\$	
				\$	
				\$	
				\$	
				\$	

C. ESTIMATED MANHOURS AND COST BY ACTION AGENCY

1. ACTION AGENCY	2. TOTAL EST. MANHOURS FOR REMEDIAL ACTIVITIES	3. TOTAL EST. COST FOR REMEDIAL ACTIVITIES	1. ACTION AGENCY	2. TOTAL EST. MANHOURS FOR REMEDIAL ACTIVITIES	3. TOTAL EST. COST FOR REMEDIAL ACTIVITIES
a. EPA			b. STATE		
c. PRIVATE			d. OTHER (specify)		

REFERENCE 14

LETTER. Subject: Administrative Order Docket No. VI-81-062. From: Diana Dutton, Director of Enforcement Division, EPA, To: Art Thomason, President, Thomason Lumber Company, April 9, 1981.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION VI
1201 ELM STREET
DALLAS, TEXAS 75270

APR 9, 81

CERTIFIED MAIL: RETURN RECEIPT REQUESTED (8081704)

Mr. Art Thomason
President
Thomason Lumber Co.
P. O. Box 804
Broken Bow, Oklahoma 74728

Re: Administrative Order Docket No. VI-81-062

Dear Mr. Thomason:

Violation of a Federal NPDES permit requires the Environmental Protection Agency to take appropriate enforcement action to assure compliance. Pursuant to the Clean Water Act (33 U.S.C. 1251 et seq.), the enclosed Administrative Order is hereby served on you and Thomason Lumber Company for the violations described therein.

Compliance with the provisions of this order is expected within the maximum time periods established by each part of the order. Your cooperation and prompt attention will be appreciated. In response hereto, please reference Docket No. VI-81-062 and send correspondence to the attention of Ms. Gay Arney (6AEL).

Since it is the policy of the Environmental Protection Agency to achieve full compliance with the NPDES permit program as rapidly as possible, this office is prepared to help you in any way it can. If you have any questions, please contact Kenneth Holley, EPA, Dallas, Texas at (214) 767-4375.

Sincerely,

Diana Dutton
Director
Enforcement Division (6AE)

Enclosure

cc: Oklahoma Water Resources Board

Thomason Lumber Co
OKD007335504

SUPERFUND FILE

JUN 18 1992

REORGANIZED

14-001

UNITED STATES
ENVIRONMENTAL PROTECTION AGENCY
REGION 6

IN THE MATTER OF

THOMASON LUMBER COMPANY

PROCEEDINGS UNDER SECTION 301(a)
and 309(a)(3), CLEAN WATER ACT
[33 USC 1311 and 33 USC 1319(a)(3)],
in RE: UNLAWFUL DISCHARGE OF
POLLUTANTS

DOCKET NO. VI-81-062

ADMINISTRATIVE ORDER

4-19-81

The following FINDINGS are made and ORDER issued pursuant to the authority vested in the Administrator of the Environmental Protection Agency by the above referenced statute (hereinafter the Act) and delegated to the Regional Administrator, Region 6, and duly redelegated to the undersigned Director, Enforcement Division, Region 6.

I.

Thomason Lumber Company (hereinafter referred to as "Company") is a company doing business in the State of Oklahoma, and having a place of business in Broken Bow, Oklahoma, the mailing address for which is P. O. Box 804, Broken Bow, Oklahoma, 74728.

Thomason Lumber Co.
OKD 00735524

II.

Pursuant to the authority of Section 402(a)(1) of the Act [33 USC 1342(a)(1)], the Regional Administrator, Region 6, issued National Pollutant Discharge Elimination System (NPDES) Permit No. OK0034207 to the Company on October 2, 1975, with an effective date of November 16, 1975. The permit was terminated on September 2, 1977.

III.

Section 301(a) of the Act prohibits the discharge of any pollutant into waters of the United States except insofar as such discharge is regulated by a permit issued pursuant to Section 402 of the Act. The Company does not currently have a NPDES permit for the discharge of any pollutant.

SUPERFUND FILE

IV.

Based upon information provided by the Environmental Protection Agency, the Company has violated Section 301(a) of the Act in that by contract inspections performed by Ecology and Environment, Incorporated, on December 4 and 15, 1980, the inspectors' reports indicate that: (1) spills from the separator tank and ponds are evident, (2) the pipeline from the separator tank to Pond A is broken, (3) final treatment Pond C contents are discharged via a pipe down the ground slope

JUN 10 1992

REORGANIZED

14-002

to a nearby intermittent creek, (4) the soil around the ponds and processing plant is highly contaminated with pentachlorophenol and cresote, and (5) the ponds used to recover pentachlorophenol and cresote are not lined.

Y.

Issuance of this Order does not preclude the pursuit of additional enforcement action for the violations cited herein.

ORDER

Based on the foregoing FINDINGS OF VIOLATION and pursuant to the authority vested in the Administrator under Section 309(a)(3) and 301(a) of the Act [33 USC 1319(a)(3) and 33 USC 1311] and duly delegated to the Regional Administrator, Region 6, and duly redelegated to the undersigned Director, Enforcement Division, Region 6, it is hereby ORDERED:

A. That the Company, upon receipt of this Order, shall immediately cease disposing of any pollutants including pentachlorophenol and cresote. The Company shall, within fourteen (14) days, submit a report to the Environmental Protection Agency confirming the cessation of this discharge.

B. Within thirty (30) days of receipt of this Order, the Company shall prepare and submit to the EPA a report for delineating the extent of the soil contaminated with pentachlorophenol and cresote and for removing and properly disposing of this contaminated soil.

C. In the event the Company wishes to discharge pollutants in the future, a permit application shall be submitted in accordance with the Consolidated Permit Regulations, 45 Federal Register 33290, dated May 19, 1980, or any applicable supersedant regulations.

The effective date of this Order shall be the date of receipt.

Dated: This _____ day of _____, 1981.

Diana Dutton
Director
Enforcement Division (6AE)

14-003

REFERENCE 15

Larry D. Wright, "Tentative Disposition", January 28, 1981.



POTENTIAL HAZARDOUS WASTE SITE
TENTATIVE DISPOSITION

REGION SITE NUMBER
6 OK 3701

File this form in the regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION OKD007335529

A. SITE NAME Thomason Lumber Co.
B. STREET Hwy. 70
C. CITY Broken Bow
D. STATE Oklahoma
E. ZIP CODE 74728

II. TENTATIVE DISPOSITION

Indicate the recommended action(s) and agency(ies) that should be involved by marking 'X' in the appropriate boxes.

RECOMMENDATION	ACTION AGENCY				
	MARK 'X'	EPA	STATE	LOCAL	PRIVATE
A. NO ACTION NEEDED - NO HAZARD					
B. INVESTIGATIVE ACTION(S) NEEDED (If yes, complete Section III.)	X	X			
C. REMEDIAL ACTION NEEDED (If yes, complete Section IV.)					
D. ENFORCEMENT ACTION NEEDED (If yes, specify in Part E whether the case will be primarily managed by the EPA or the State and what type of enforcement action is anticipated.)					

E. RATIONALE FOR DISPOSITION

Site appears to be sloppily operated with possible discharges of creosote/PCP to nearby creek. Soils are moderately permeable, although groundwater in area not used for drinking water supply. Samples were collected, and a final strategy will be determined based on the results of analysis.

F. INDICATE THE ESTIMATED DATE OF FINAL DISPOSITION (mo., day, & yr.)

March 31, 1981

G. IF A CASE DEVELOPMENT PLAN IS NECESSARY, INDICATE THE ESTIMATED DATE ON WHICH THE PLAN WILL BE DEVELOPED (mo., day, & yr.)

H. PREPARER INFORMATION

NAME Larry D. Wright
2. TELEPHONE NUMBER FTS 729-3274
3. DATE (mo., day, & yr.) 1-28-81

III. INVESTIGATIVE ACTIVITY NEEDED

A. IDENTIFY ADDITIONAL INFORMATION NEEDED TO ACHIEVE A FINAL DISPOSITION.

Samples analyses of:

1. Material in pond prior to discharge.
2. Soil sample from drainage path between pond and creek.
3. Upstream and downstream creek sediment samples.

B. PROPOSED INVESTIGATIVE ACTIVITY (Detailed Information)

1. METHOD FOR OBTAINING NEEDED ADDITIONAL INFO.	2. SCHEDULED DATE OF ACTION (mo., day, & yr.)	3. TO BE PERFORMED BY (EPA, Contractor, State, etc.)	4. ESTIMATED MANHOURS	5. REMARKS
A. TYPE OF SITE INSPECTION				SUPERFUND FILE
(1)				
(2)				JUN 10 1992
(3)				REORGANIZED
B. TYPE OF MONITORING				
(1)				
(2)				15-001
C. TYPE OF SAMPLING				
(1)				

REFERENCE 16

Amy Layne, EPA, "Tentative Disposition", November 29, 1985.



POTENTIAL HAZARDOUS WASTE SITE
TENTATIVE DISPOSITION

REGION SITE NUMBER
6 OK03701

File this form in the regional Hazardous Waste Log File and submit a copy to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION OKD007335524

A. SITE NAME THOMASON LUMBER COMPANY
B. STREET ON HUFFMAN ROAD - 0.5 mi. SOUTH OF Hwy 70
C. CITY BROKEN BOW (MCCURTAIN COUNTY)
D. STATE OK
E. ZIP CODE 74728

II. TENTATIVE DISPOSITION

Indicate the recommended action(s) and agency(ies) that should be involved by marking 'X' in the appropriate boxes.

RECOMMENDATION	MARK 'X'	ACTION AGENCY			
		EPA	STATE	LOCAL	PRIVATE
A. NO ACTION NEEDED - NO HAZARD					
B. INVESTIGATIVE ACTION(S) NEEDED (If yes, complete Section III.)			X		
C. REMEDIAL ACTION NEEDED (If yes, complete Section IV.)					
D. ENFORCEMENT ACTION NEEDED (If yes, specify in Part E whether the case will be primarily managed by the EPA or the State and what type of enforcement action is anticipated.)					

E. RATIONALE FOR DISPOSITION

Thomason Lumber Company apparently entered into a consent agreement in March of 1985, with OWRB for site cleanup and closure. The site is also under investigation by OSDH/RCRA as a possible non-notifier. If OSDH/RCRA and OWRB efforts fail to result in effective remedial actions, OSDH should renew investigation under the PA/ST program. A followup inspection will be necessary to ensure that appropriate cleanup has been achieved.

F. INDICATE THE ESTIMATED DATE OF FINAL DISPOSITION (mo., day, & yr.)

G. IF A CASE DEVELOPMENT PLAN IS NECESSARY, INDICATE THE ESTIMATED DATE ON WHICH THE PLAN WILL BE DEVELOPED (mo., day, & yr.)

H. PREPARER INFORMATION

1. NAME Amy M. Layne, 6H-ES
2. TELEPHONE NUMBER (214) 767-6421
3. DATE (mo., day, & yr.) 11/29/85

III. INVESTIGATIVE ACTIVITY NEEDED

A. IDENTIFY ADDITIONAL INFORMATION NEEDED TO ACHIEVE A FINAL DISPOSITION.

A final strategy recommending no further action can be achieved if followup inspection reveals that appropriate cleanup and closure has been achieved.

B. PROPOSED INVESTIGATIVE ACTIVITY (Detailed Information)

1. METHOD FOR OBTAINING NEEDED ADDITIONAL INFO.	2. SCHEDULED DATE OF ACTION (mo., day, & yr.)	3. TO BE PERFORMED BY (EPA, Contractor, State, etc.)	4. ESTIMATED MANHOURS	5. REMARKS
A. TYPE OF SITE INSPECTION				SUPERFUND FILE
(1) Recon SIF	FY86	(OSDH) STATE*		JUN 10 1986
(2)		**		REORGANIZED
(3) *				
B. TYPE OF MONITORING				
(1)				If OSDH/RCRA and OWRB efforts fail to bring about remedial cleanup of the site, OSDH can pursue investigation under the PA/ST program.
(2) **				Or FIT, if State actions are not possible.
C. TYPE OF SAMPLING				
(1)				16-001
(2)				

REFERENCE 17

RECORD OF COMMUNICATION: Subject: Fish Production. From: Ariadne Lytwyn, Geologist, Fluor Daniel, Inc., To: Jack Harper, Ok Dept. Wildlife, March 25, 1994.

FLUOR DANIEL

RECORD OF TELEPHONE CONVERSATION

FROM: Ariadne Lytwyn <i>AL</i>	DATE: March 25, 1994
LOCATION: FD - Chicago	TIME: 9:18 pm
TO: Jack Harper	P.O. NO.
LOCATION: Ok Dept. of Wildlife	OTHER REF:

Oklahoma does not keep records for amount of fish caught a year. However, fishing does occurred in the Little River. The types of fish caught for human consumption are large-mouth bass, channel catfish and bluegill fishes.

17-001

REFERENCE 18

U.S. Environmental Protection Agency, "Hazard Ranking System Guidance Manual",
OSWER Directive 9345.1-07, November 1992, p. 314.

The Hazard Ranking System Guidance Manual

Interim Final

**Hazardous Site Evaluation Division
Office of Solid Waste and Emergency Response
U.S. Environmental Protection Agency
Washington, DC 20460**

18-001

ESTIMATING PRODUCTION USING SURROGATE DATA

If estimates of annual production data specific to the fishery are not available, estimate production by collecting information for similar surface water bodies containing comparable fisheries. Determine if the surrogate fishery (and the water body itself) is similar to the fishery being evaluated in terms of

- Fish species or other human food chain organisms present (e.g., production data for a fishery consisting primarily of pike should not be used when evaluating a fishery consisting primarily of smallmouth bass);
- Flow rate (or depth for oceans);
- Characteristics (e.g., salinity, flow, depth, subsurface bottom, state classification, overall water quality);
- Distance from each water body to possible surrogate water body; and
- Fishing activities.

Consider these criteria before assuming that production data from a similar water body can be used for estimating production for the fishery (or portions of the fishery) within the TDL. State fish and game officials are a likely source for such information. Document the rationale for using surrogate data from another fishery for the fishery being evaluated.

For example, production data for a fishery consisting primarily of trout could be used for a fishery consisting of trout that is 30 miles away. The average annual flows of both water bodies should be similar even though the surface water dilution weight assigned to each water body may be different (e.g., a small to moderate stream may have a flow of 90 cfs (an assigned dilution weight of 0.1) while an acceptable surrogate fishery may be a moderate to large stream having a flow of 140 cfs (an assigned dilution weight of 0.01)). In addition, the characteristics of both the surrogate water body and the water body within the TDL should share similar attributes. Both should be either managed as a high quality cold-water fishery or be managed as a limited warm-water fishery. Likewise, both should be either annually stocked and aggressively managed for sport fishing or not stocked.

ESTIMATING PRODUCTION WITHOUT ACTUAL OR SURROGATE DATA

If surface water is documented to be a fishery and production data (actual and surrogate) are not available, assign the fishery a minimum human food chain production of greater than 0 pounds per year. Then, assign the fishery a human food chain population value of 0.03 based on HRS Table 4-18. Use this human food chain population value to assign factor values for Level I concentrations, Level II concentrations, and potential human food chain contamination. Show that the fishery supports human food chain organisms by documenting that at least one human food chain organism lives within fishery boundaries and that fishing occurs in the surface water body.

18-002